

UNION NATIONAL BANK BLDG., WICHITA, KANSAS.

Location NE cor NW, SW.

Sec. 2 T. 11 R. 21W.

Plotted

Casing Record


10" 1551 Farm- Eaton
 20" 65' 8 1/2" 2863 Company- R. E. Day.
 15 1/2" 525 65/8" 3834 Contr.-
 12 3/8" 927 53/16" Comm.- 5/31/1929.

County- Trego

No. 1

Comp.- 3/3/1930

Total Depth 3871'. Shot Quarts Between
 Correspondence Regarding This Well Should Be Referred to



Elevation 2088'

Figures Indicate Bottom of Formations.

Initial Production Dry.

Date Issued. 3/29/1930.

Formation	Depth	Formation	Depth	Formation	Depth
cellar	13	salt	2065	lime white hrd	3070
sand gray sft	23	brkn lime & sh.		brkn lime & shale	
Ft. Hays lime white	45	blue med.	2095	med	3105
sand white sft HFV	65	lime gray	2115	shale blue sft	3160
shale blue med	300	brkn lime & sh		lime white hrd	3190
shale brown med	460	blue	2150	HFV 3195'	
shale gray sft HFV	525	lime white hrd	2165	shale lgt sft	3191
sand water white med	550	shale red sft	2170	lime white hrd	3275
shale lgt med	580	lime white med	2175	brkn lime & shale	
red rock red	595	shale red sft	2180	med (1 BW 3345-60)	3360
shale gray sft	605	lime white hrd	2198	shale blue med	3375
red rock red sft	635	shale blue sft	2210	shale red sft	3390
shale gray sft	645	shale red sft	2225	lime hrd	3428
lime & pyrite gray med 648		lime gray hrd	2260	shales brkn blue	
shale blue sft	665	shale red med	2280	sft	3443
sand water gray sft	715	lime gray med	2295	Top of Oswald lime	3443'
HFV Fresh 715'		lime gray hrd	2315	lime hrd	3449
shale blue sft	720	shale blue med	2330	lime sdy hrd	3453
sand gray sft	795	lime gray hrd	2373	shale red & blue	
HFV Fresh 795		shale blue med	2383	sft	3456
shale blue med	805	brkn lime & shale red		lime hrd	3485
shale black sft	812	med	2435	Good show oil	3470-75'
shale blue med	880	lime sdy white sft	2445	shale blue sft	3485
shale green med	885	1 1/2 BW per hr		3 BW 3486'	
iron hrd	889	lime gray hrd	2470	lime shell	3486
shale blue med	895	brkn lime & shale		shale blue sft	3500
lime white med	900	red med.	2495	lime white hrd	3523
shale gray med	912	lime gray hrd	2520	shale blue & red	
iron hrd	923	shale red sft	2525	sft	3432
sand gray hrd	940	lime gray hrd	2530	lime hrd	3552
shale blue med	945	shale red sft	2540	shale blue & red	
shale white med	960	lime gray hrd	2550	sft	3556
red rock red med	965	shale red sft	2575	lime brkn med	3563
sand gray med	975	5 BW 2585-90'		lime sft	3566
shale green med	980	lime gray med	2610	Good show oil	3563-66
sand white sft	1000	shale red sft	2615	shale blue sft	3574
Salt water @ 1000'		lime gray hrd	2620	lime white hrd	3585
red rock red sft	1030	shale red sft	2635	lime & shale blue	
sand gray sft	1230	lime white med	2655	med	3591
HFV S water		HFV 2635-2655'		lime gray hrd	3614
shale red med	1255	lime gray med	2665	shale blue sft	3626
sand sft red	1275	shale black sft	2667	lime white med	3640
shale red hrd	1375	lime white hrd	2710	lime	3649
shale red sft	1547	shale blue sft	2715	lime brkn	3661
chalk white sft	1551	lime white hrd	2725	lime hrd	3665
10" csg. at 1409 Reamed		brkn lime & shale blue		shale green	3684
10" to 1551'		med	2760	Correction bottom 9'	
lime white hrd	1605	lime white med	2775	lime gray hrd	3688
shale red sft	1700	1 1/4 BW per hr 2775'		Smell of gas	
shale blue med	1725	brkn lime & shale blue		lime red sft	3772
shale red sft	1815	hrd	2845	lime smell of gas	3608
shale blue sft	1835	shale blue med	2860	sand show of oil	3625
lime gray hrd	1840	brkn lime & shale blue		shale green sft	3826
shale blue sft	1885	med	2885	more water	
lime gray hrd	1905	lime white hrd	2895	lime gray hrd	3840
shale blue sft	1910	shale blue med	2912	sand HFV white med	3862
lime brkn gray med	1925	lime white hrd	2920	Oil rainbow	3840
salt med	1950	slate blue med	2975	shale green sft	3863
brkn salt & sh. blue		lime white hrd	2985	sand white	3867
med	1980	shale blue sft	3010	lime	3871
				T.D. 3871'	