

WICHITA, KANSAS
DRILLERS' WELL LOG

13-115-21w

ST. FRANCIS #1
Sec. 13-115-21W
Trago County, Kansas

15-195-20264

COMMENCED: March 4, 1974
COMPLETED: March 14, 1974

OPERATOR: FRANK EXPLORATION

DEPTH		FORMATION	REMARKS
From	To		
0	243	Surface Clay-Sand-Shale	Ran 14 jts. of used 8-5/8" csg.
243	1310	Shale-Sand	(242.88 overall) set @ 239'
1310	1513	Redbed-Shale	cemented w/175 sacks common
1513	1622	Shale-Redbed	cement, 2 1/2 Gal, 3% CC.
1622	1888	Anhydrite	P.D. @ 5:30 AM, March 4, 1974.
1888	2090	Shale	
2090	3253	Lime-Shale	Ran 125 jts. of used 4-1/2" csg.
3253	3792	Lime	set @ 3722' cemented w/175 sacks
			common cement, 7 1/2 Salt.
			P.D. @ 10:50 AM, March 14, 1974.
3792 Total Depth			

I, James S. Sutton II, certify this is a correct copy of the Drillers' Log for the well drilled in the SE/4 of Sec. 13-115-21W, Trago County, Kansas to the best of my knowledge and belief.

James S. Sutton II
JAMES S. SUTTON II

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS

Before me, the undersigned, a Notary Public within and for said County and State, on this 18th day of March, 1974, personally appeared James S. Sutton II to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and at last above written.

Marjorie Hall
MARJORIE HALL - NOTARY PUBLIC

My Commission Expires: November 29th, 1975.

REC'D
STATE CORP COMM.
7-16-75
CONSERVATION DIV.
Wichita, Ks.

RECEIVED
STATE CORPORATION COMMISSION

JUL 16 1975

