

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- HARRY GORE-VEEDER SUPPLY & DEV. CO.
Farm- Findlay No. 1

SEC. 23 T. 11 R. 21W
SE NE NE

Total Depth. 3788'

Comm. 6-25-54

Comp. 7-12-54


Shot or Treated.

Contractor. Veeder Supply & Dev. Co.

Issued. 8-28-54

County Trego

KANSAS



CASING:

8 5/8" 219' w/150 sx cem.

5 1/2" 3785' w/100 sx Cem.

Elevation. 2211' R. B.

Production. 83 BO

Figures indicate Bottom of Formations.

sand	44
gray shale	140
white shale	219
blue shale	390
gray shale	685
sand	700
gray shale	745
sand	870
shale-sand strks	1120
sand	1350
shale	1380
shells-shale-redbed	1630
anhydrite	1685
shale-lime	3255
lime	3330
lime-shale	3425
lime	3610
lime-shale	3650
lime	3788
Total Depth	

TOPS:

Topeka	3240
Heebner	3450
Toronto	3472
Lansing	3490
Base Kansas City	3713
Arbuckle	3734