

DARBY PETRO. CORP.
Haneke No. 1.

SEC. 24 T. 11 R. 21 W
SE NW SE

Total Depth. 3850'
Comm. 3-21-42 Comp. 4-15-42
Shot or Treated.
Contractor.
Issued. 4-25-42

County. Trego



CASING:
8" 1632'
5" 3831' Ctd

Elevation.

Production. Dry

Figures Indicate Bottom of Formations.

shale & shells	785
shale, shells & iron	890
shale & shells	995
gumbo	1005
iron & sand	1080
shale & shells	1310
sand	1330
shale, shells & red bed	1485
red bed	1620
shale red	1624
gypsum	1626
anhydrite	1680
shale & shells	2080
salt	2140
shale & shells	2345
lime brkn	2395
shale & shells	2585
lime & shale	2600
lime	2705
shale	2900
lime & shale	3260
lime	3290
lime & shale	3335
lime	3490
lime & shale	3520
lime	3743
shale	3765
shale & lime	3790
lime	3820
dolomite	3842
lime sdy	3850
Total Depth.	

Top Arbuckle 3816 Ctd

slight stain & porosity 3505-15
dead stain 3545-50
slight stain 3589-95 & 3600-06
slight stain 3701-05 & 3709-13
poor porosity & fair sat. 3831-38
fair porosity & fair sat. 3838-40

Drilling cement @ 3839

350' water and scum oil @ 3841
600' " 3850

VIEW - D & A