

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY

505 East Murdock,

Wichita, Kansas


Company- **IMPERIAL OIL OF KANSAS, INC.**
 Farm- **Huck** No. **1**

SEC. **25** T. **11** R. **21W**
 SE NE NE

Total Depth. **3905'**
 Comm. **5-2-60** Comp. **5-16-60**

County **Trego**
KANSAS

Driller Treated.
 Contractor. **Imperial Oil of Kansas, Inc.**
 Date. **8-13-60**

**CASING:**

8 5/8" @ 220' w/175 sks. cem.
5 1/2" @ 3903' w/125 sks. cem.

Elevation **2296'** RB

Production. **182 BOPD**

Figures indicate Bottom of Formations.

surface clay & sand	220
shale & sand	1450
shale & shells	2300
lime & shale	3325
lime	3867
lime, chert & shale	3882
cherty lime	3900
Arbuckle (cherty)	3905 RTD
Total Depth	

TOPS:	ELECTRIC	
	SAMPLE	LOG
Heebner	3539	3538
Toronto	3563	3564
Lansing	3576	3575
Base Kansas City	3810	3809
Marmaton Sand	3846	3844
Conglomerate	3875	3874
Reworked Arbuckle	3895	
Arbuckle	3898	

Drill Stem Tests:

#1	3597-3626 (35' Zone)
	3638-3642 (50' Zone)
#2	3624-3641 (50' Zone)
	3650-3656 (70' Zone)
#3	3638-3653 (70' Zone)
	3659-3664 (90' Zone)
#4	3658-3665 (90' Zone)
	3671-3673 (100' Zone)
#5	3667-3686 (100' Zone)
	3712-3718 (140' Zone)
#6	3704-3726 (140' Zone)
	3734-36 & 3740-44 (160' Zone)
#7	3728-3748 (160' Zone)
	3752-3754 (180' Zone)
#8	3747-3767 (180' Zone)
	3755-3767 (180' Zone)
	3772-74 & 3777-83 (200' Zone)
#9	3762-3788 (200' Zone)
	3794-3795 (220' Zone)
#10	3899-3905 (Arbuckle)