

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,


Wichita, Kansas

Company- Imperial Oil Company
Farm- Huck

No. 3

SEC. 25
C W $\frac{1}{2}$ NE NE

R. 21W

Total Depth. 3928'
Comm. 12-19-62 Comp. 1-3-63
Shot or Treated.
Contractor. Imperial Oil of Kansas, Inc.
Issued. 4-6-63County Trego
KANSASCASING:
8 5/8" 221' cem w/175 sx.
4 1/2" 3927' cem w/150 sx.

Elevation. 2299' KB

Production. 66 BOPD

Figures indicate Bottom of Formations.

| | |
|---------------------|----------|
| surface rock & sand | 221 |
| sand & shale | 1225 |
| Dakota sand | 1420 |
| sand | 1485 |
| shale & red bed | 1700 |
| Anhydrite | 1744 |
| shale & shells | 2390 |
| shale & lime | 3565 |
| lime & inert | 3601 |
| lime | 3883 |
| chert & lime | 3903 |
| chert & shale | 3918 |
| chert | 3928 RTD |
| Total Depth | |

| TOPS: | SAMPLE | ELECTRIC |
|------------------|--------|----------|
| Heebner | 3540 | 3539 |
| Toronto | 3564 | 3563 |
| Lansing | 3575 | 3576 |
| Base Kansas City | 3808 | 3808 |
| Conglomerate | 3875 | 3875 |

DST #1 3600-20', op 2 hrs, very weak blow
Rec. 30' OCM w/free oil in the tool. ICIP 298#,
FCIP 67#/20 mins.

DST #2 3641-56', op 1 hr, very weak blow, Died
intermittently. Rec. 5' HOCM, 20' oil specked
mud. ICIP 410#, FCIP 52#/20 mins and 30 mins shut
in time.

DST #3 3658-66', op 30 mins, very weak blow; died
in 5 mins. Rec. 10' slightly oil cut water, ICIP
298#, IFP 14#, FFP 37#, FCIP 298#/20 mins.

DST #4 3695-3720', op 30 mins, weak blow, died
in 5 mins. Rec. 5' oil specked mud w/free oil
in the tool. ICIP 311#, FCIP 74#/20 mins.

DST #5 3722-40', op 30 mins, very weak blow.
Died in 3 mins. Rec. 5' oil specked mud. All
pressures-zero, shut in 20 mins.

DST #6 3762-86', op 2 hrs, very weak blow. Rec.
10' muddy oil, 25' slightly oil cut mud. ICIP
1045#, IF 22#, FF 52#, FCIP 223#/20 mins.

DST #7 3867-3903', op 30 mins, very weak blow,
died in 5 mins. Rec. 5' oil specked mud.
ICIP 186#, FCIP 29#/20 mins.