

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


Company- STANOLIND OIL & GAS CO.
Farm- Walter Huck No. 1

SEC. 25 T. 11 R. 21W
SW NW NW

Total Depth. 3899'
Comm. 2-13-55 Comp. 2-26-55
Shot or Treated.
Contractor.
Issued. 4-9-55

County Trego

KANSAS



8 5/8" CASING:
237' cem w/150 sx

Elevation. 2250' RDB

Production. Dry

Figures Indicate Bottom of Formations.

sand	150
clay	475
shale	800
red bed	810
shale	1000
sand	1100
sand, red bed	1310
red bed, shale	1640
red bed	1660
anhydrite	1855
shale	2110
shale and shells	2215
lime, shale	2520
shale	2530
shale; shells	2700
shale, lime	2815
shale	3020
lime, shale	3105
shale	3175
lime, shale	3331
lime	3380
lime, shale	3505
lime	3725
shale	3760
lime	3899
Total Depth	

Tops:
Arbuckle 3835

DRILL STEM TESTS:

#1 3830'-3838', tool open 45 mins., closed
20 mins. Rec. 20' Drl mud NS - BHPF 0#
BHPSI 40#.

Core #1 3835'-3838' - Rec. 3'0" Dense SHYLMNS.

Core #2 3838'-3843' - Rec. 2'-6" - 0'-6"
Redish Brn. SH - 0'6" Redish Brn.
SNYSH - 1'-6" Green Sh x Stks of Lm.