


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- ROCK ISLAND OIL & REFINING
Farm- Hale No. 1

SEC. 26 T. 11 R. 21W
NE SE SW

Total Depth. 3938'
Comm. 12-12-63 Comp. 12-23-63
Shot or Treated.
Contractor. Gabbert-Jones, Inc.
Issued. 3-14-64

County Trego
KANSAS



CASING:

8 5/8" 244' cem w/ 140 sx

Elevation. 2308' DE

Production. DRY

Figures indicate Bottom of Formations.

surface clay	30
shale & sand	92
sand	220
shale	244
shale & sand	1120
shale & shells	1700
shale & lime	3400
lime	3560
lime & shale	3765
lime	3853
lime & shale	3938 RTD
Total Depth	

TOPS: SMP

Topeka	3347
Heebner	3556
Toronto	3578
Lansing	3597
Base Kansas City	3810
Arbuckle	3911

DST #1 3599-3647 Failed

DST # 2 3587-3647 Failed

DST # 3 3660-3691 Op 1 hr. fair blow.
Rec. 180' water mud and 180' muddy water.
IBHP 638/20 min; IFP 39.; FFP 211; FBHP
565 20 min.

DST # 4 3913-3918' Op 20 min Weak blow
4 min. Rec. 5' mud. IBHP 925 20 min.
IFP 2 3; FFP 39; FBHP 699 20 min.

DST # 5 3918-3938' Op 1 hr. Strong blow.
Rec. 2400' sulphur water. IBHP 1149
20 min; IFP 361; FFP 1101; FBHP 1133
20 min.