

3-1122W

WILLIAMSON DRILLING, INC.

5501 NAVAJO

GREAT BEND, KANSAS 67530

X Ind

DRILLERS' WELL LOG

DATE COMMENCED: August 17, 1985

DATE COMPLETED: August 21, 1985

Rockhound Resources, Inc.
Demurray #1
NE NE NE
Sec 3, Twp 11, Rge 20E
Trego County, Kansas

Elevation: 2202 G.L.
2207 K.B.

Surface Pipe: 8 5/8" surface pipe was
already set at 174' and cemented.

Production Casing: Ran 92 Jts. New 10.5"
4 1/2" casing, set at 3859'. Circulated
cement from 3859- G.L. w/800 sks. Lite
cement and 150 sks. Sure-Fill.

- 0-1300' Surface Soil, Post Rock,
Sand, Clay, Shale
- 1300-1692' Redbed
- 1692-1730' Anhydrite
- 1730-3210' Shale w/Lime Stringers
- 3210-3450' Lime w/Shale Stringers
- 3450-3456' Shale
- 3456-3770' Lime w/Shale Stringers
- 3770-3800' Conglomerate
- 3800-3826' Dolomitic Cherts
- 3826-3860' Shale
- 3860' R.T.D.

MAY 12 1985

KANSAS GEOLOGICAL SURVEY
GREAT BEND OFFICE

A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON ss

Terry L. Williamson of lawful age, does swear and state that the facts