

P. 5-11-22W

WAYNE DOBBS, INC.

TELEPHONE (316) 793-3282

P. O. BOX 315

GREAT BEND, KANSAS 67530

RECEIVED
STATE CORPORATION COMMISSION

WELL COMPLETION

MAR 05 1984

Mustang Drilling--Petromark Exploration
Drawer 1609
Great Bend, Kansas 67530

CONSERVATION DIVISION
Wichita, Kansas

P.O. 3728

RE: ✓ Faulkner # 1
SE SE NW
Sec. 5 T11 R22W
Trego County, Ks.

- Apr. 25, 1984 Drove to location & unloaded tubing & portable pump---double drum unit had engine trouble before getting to location.
- Apr. 26, 1984 Drove to location & wait on unit---unit had problem getting out of old location & didn,t arrive until 6:00 p.m.
- Apr. 27, 1984 Rig up---ran tubing & 4 7/8" bit in hole---drilled plug, insert, & 35' cement out of shoe joint---come out of hole with tubing & bit---perforate 3722' with 1 shot & 3701' with 1 shot---start tubing & packer in hole---S.D.
- Apr. 28, 1984 Finished running tubing & packer in hole---spot acid over perforations then moved packer up hole to 3678'--acidized with 600 gal. 28% NE---max. rate 5 b.p.m. at 1900#---overflushed 10 bbl.---total load 40 bbl.---ISIP 500# down to 250# in 20 min.---left well shut in 2 hours---release pressure off tubing & start swabbing hole down---swab to bottom rec'd 15.95 bbl. fluid with show oil last 2 pulls---30 min. S.T. rec'd 1.16 bbl. fluid 37.5% oil---30 min. S.T. rec'd 1.16 bbl. fluid 41.6% oil---30 min. S.T. rec'd small amount fluid TSTM 55.5% oil---1 hour S.T. rec'd .58 bbl. fluid 64.2% oil---total fluid swabbed back 18.85 bbl.
- Apr. 30, 1984 Approx. 1700' fluid in hole (3.48 bbl. oil & 2.32 bbl. water) 60% oil---30 min. S.T. rec'd .58 bbl. fluid .95% oil---30 min. S.T. rec'd .29 bbl. fluid all oil---30 min. S.T. was dry---30 min. S.T. rec'd .29 bbl. oil---30 min. S.T. was dry---30 min. S.T. rec'd .58 bbl. oil---1 hour S.T. rec'd .29 bbl. oil---acidized with 2000 gal. 15% NE---max. rate of 5 b.p.m. at 1900#---total load 67½ bbl.---ISIP 500# down to 225# in 15 min.---shut well in 30 min.---released pressure on tubing and start swabbing hole down---made 2 pulls with swab in 30 min. rec'd 2.61 bbl.