

15-195-20456

CONTRACTOR'S WELL LOG

16-11-22W

WICHITA BRANCH

OPERATOR:
CONTRACTOR:
WELL NAME:
LOCATION:

SPUD DATE:
COMPLETION DATE:

F & M Oil Co., Inc.
Abercrombie Drilling, Inc.
Spring Valley "A" #2
NE NE NW Section 16-11S-22W
Trego County, Kansas
February 28, 1978
March 9, 1978

0	20	Clay, sand & post rock
20	215	Shale & sand
215	1612	Shale
1612	1663	Anhydrite
1663	2299	Shale
2299	2535	Lime & shale
2535	2619	Shale
2619	3016	Lime & shale
3016	3220	Shale
3220	3435	Lime & shale
3435	3470	Lime
3470	3505	Shale & lime
3505	3535	Lime
3535	3583	Shale & lime
3583	3670	Lime
	3670	Rotary Total Depth

Spud at 2:30 p.m., February 28, 1978. Drilled 215' of 12 1/4" hole. Ran 5 joints of 8-5/8" casing, set at 212.49'. Cemented with 175 sacks of common cement, 2% gel, 3% CaCl. Cement did circulate. Plug was down at 8:30 p.m., February 28, 1978.

T.D. 3670'. Ran 96 joints of 4 1/2" - 9 1/2# casing. Set at 3670'. Cemented with 100 sacks of common cement. Plug was down at 7:30 a.m., March 9, 1978.

SAMPLE TOPS:

Anhydrite 1612'
B/Anhydrite 1663'

STATE OF KANSAS)
) ss
COUNTY OF SEDGWICK)

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Spring Valley "A" #2, NE NE NW Section 16-11S-22W, Trego County, Kansas.

ABERCROMBIE DRILLING, INC.