

KANSAS

WICHITA BRANCH

WELL COMPLETION REPORT AND
DRILLER'S LOG

REACH PETROLEUM CORP.


API No. 15 — 195 — 20,328
County Number

ELECTRIC LOG

S. 20 T. 11S R. 22W E
W

Loc. 100' N W/2 NW SE

County Trego

640 Acres
N

Locate well correctly

Elev.: Gr. 2333

DF 2339 KB 2341

Operator

Reach Petroleum Corporation

Address

3751 E. Douglas, Wichita, KS 67218

Well No.

#1

Lease Name

Uhrich

Footage Location

2080 feet from (XX) (S) line 2310 feet from (E) (XX) line

Principal Contractor

Reach Drilling

Geologist

Richard S. Davis, Jr.

Spud Date

6/6/81

Date Completed

7-31-81

Total Depth

4040

P.B.T.D.

3994'

Directional Deviation

None.

Oil and/or Gas Purchaser

Clear Creek

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface		8 5/8"		269'	common	165	2% gel 3% CaCl
Production		4 1/2"		4036'	Halliburton	700	
					60-40 posmix	300	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2		3941-47
Size	Setting depth	Packer set at			


ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Frac w/39,000 gal gelled water w/200 sx 20-40 and 50 sx 10-20 sand	3941-47


INITIAL PRODUCTION

Date of first production	8-10-81	Producing method (flowing, pumping, gas lift, etc.)	Pumping
RATE OF PRODUCTION PER 24 HOURS	Oil 98 bbls.	Gas N/A MCF	Water None bbls.
Disposition of gas (vented, used on lease or sold)	N/A	Producing interval(s)	Marmaton

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Reach Petroleum Corporation		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: Oil	
Well No. #1	Lease Name Uhrich		
S 20 T 11 S R 22 W E W			
WELL LOG Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME
Anhydrite Topeka Heebner Toronto Lansing A Lansing B Dennis Swope Hertha Marmaton Arbuckle	1800 3542 3574 3596 3613 3651 3785 3808 3831 3929 4027		
DST #1, 3569-3610', Toronto, 30-30-30-30, Rec. 10' OSM, IHP 2314 psi., IFP 48-48 psi., ISIP 708 psi., FFP 58-48 psi., FSIP 759 psi., FHP 2122 psi., BHT 110°F.			
DST #2, 3635-62', Lansing B, 30-60-30-60, Rec. 600' MSW, IHP 2604 psi., IFP 59-118 psi., ISIP 733 psi., FFP 153-212 psi., FSIP 732 psi., FHP 2009 psi.			
DST #3, 3935-65', Marmaton, 30-60-30-60, Rec. 130' MCGO (2% W, 8% M, 10% G, 80% O), IHP 2264 psi., IFP 68-88 psi., ISIP 1228 psi., FFP 88-98 psi., FSIP 1169 psi., FHP 2314 psi., BHT 115°F.			
DST #4, 4019-4040', Arbuckle, 30-30-30-30, Rec. 1' 0 specked mud, IHP 2307 psi., IFP 24-24 psi., ISIP 59 psi., FFP 12-12 psi., FSIP 111 psi., BHP 2188 psi..			
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.			
Date Received	 Michael R. Bryan Exploration Manager		
	Title 11-16-81 Date		

95023



REACH DRILLING CORPORATION

3751 E. Douglas
Wichita, KS. 67218

June 15, 1981

RE: Uhrich #1
W/2 NW SE
Sec. 20 T11S-R22W
Trego County

OPERATOR: Kansas Oil Corporation

CONTRACTOR: Reach Drilling Corporation

DRILLING DATES: June 6 thru June 14

Surface Pipe 269' 12 1/4" w/165 2% cc 3% Gel

0	299	Shale & Sand
299	1079	Shale
1079	1800	Shale & Sand
1800	1844	Anhydrite
1844	2887	Shale & Lime
2887	4040	Lime & Shale

RECEIVED
STATE CORPORATION COMMISSION
JUN 20 1981
CONSERVATION DIVISION
Wichita, Kansas

We certify that the above and foregoing is a true and correct copy of the log on the Uhrich #1 in Trego County, Kansas.

REACH DRILLING CORPORATION

Floyd C. Wilson

Floyd C. Wilson
President

Subscribed and sworn to before me this 15th day of June, 1981.



Jane Stansbury
Notary Public