

KANSAS CONFIDENTIAL
**WELL COMPLETION REPORT AND
 DRILLER'S LOG**

State Geological Survey
 WICHITA BRANCH

S. 28 T. 11 R. 22W E W

Loc. SW NW SE

County Trego

API No. 15 — 195 — 20,684
 County Number

Operator

Kansas Oil Corporation

Address

250 N. Rock Rd. Suite 300, Wichita, KS 67206

Well No.

#2 B

Lease Name

Honas

Date: 1 OCT 1982

FROM CONFIDENTIAL

Footage Location

1650

feet from XXX (S) line

2310

feet from XXX (W) line

Principal Contractor

Spartan Drilling

Geologist

Zeb Stewart

Spud Date

8/4/80

Date Completed

10/3/80

Total Depth

4050'

P.B.T.D.

Directional Deviation


None.

Oil and/or Gas Purchaser

Clear Creek

Elev.: Gr. 2347'

DF 2352' KB 2355'



CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface		8 5/8"		352.8'	common	185	2% gel 3% CaCl
Production		4 1/2"		4042'	common	650	2% gel 3% CaCl
					60-40 posmix	300	2% gel 3% CaCl

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2		3650-3654
			2		3945-3954

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
ON FU 1000' SW w/show of oil. Swb 6.5 BFPH, 10% O	3650-54
Frac w/38,000 gals KCL water + 28,000 # sand. Treated @ 21 BPM @2200 psi. Shut-in. Swb back. Swb 27 BFPH, 50% oil. Swb Lansing B and Marmaton together. Swb. 33 BFPH, 50% oil for 4 hours.	3945-3954

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
10/9/80		pumping			
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	30 BOPD bbls.	N/A	30 BPD bbls.	N/A	CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval(s)		
N/A			3945-3954		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Kansas Oil Corporation		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: /	
Well No. #2 B	Lease Name Honas		Oil
S 28 T 11 R 22W^E_W			
WELL LOG Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME
Anhydrite Heebner Toronto Lansing A Lansing B Marmaton Total Depth	1795 3579 3598 3616 3653 3943 4050		
DST#1, 3608-3638, Lansing A zone, 30-60-30-60, Rec. 60' oil specked mud, IHP 1814 psi., IFP 48-51 psi., ISIP 51 psi., FFP 51-61 psi., FSIP 71 psi.,			
DST#2, 3628-64, Lansing B zone, 30-30-30-30, Rec. 37' 0, 81' M, 502' W, IHP 1864 psi., IFP 102-277 psi., ISIP 565 psi., FFP 236-329 psi., FSIP 555 psi., FHP 1843 psi.			
DST#3, 3944-80, Marmaton, 30-30-30-30, Rec. 27' M, and 3' 0, IHP 2051 psi., IFP 51-51 psi., ISIP 1022 psi., FFP 51-51 psi., FSIP 1845 psi., FHP 2030 psi.			
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.			
Date Received	 Signature Michael R. Bryan Title 6/10/81 Date		

05375


PI

28-11-22W



State Geological Survey
WICHITA, BRANCH

August 26, 1980



DRILLERS LOG

RE: Honas "B" #2
SW/NW/SE
Sec. 28 T11-R22W
Trego County, KS

OPERATOR: Kansas Oil Corporation
CONTRACTOR: Spartan Drilling Corporation
COMMENCED: 8-4-80
COMPLETED: 8-13-80

Surface Pipe 285 ft. 12 $\frac{1}{4}$ " w/225 sx common 3% cc 2% gel

0	372	Shale & Sand
372	1782	Shale
1782	1838	Anhydrite
1838	3052	Shale & Lime
3052	3664	Lime & Shale
3664	4050	Lime & Shale

We certify that the above and foregoing is a true and correct copy of the log on the Honas "B" #2 in Trego County, Kansas.

Spartan Drilling Corporation

Floyd C. Wilson
Floyd C. Wilson
President

Subscribed and sworn to before me this 26th day of August, 1980.



Carol E. Wilson
Carol E. Wilson, Notary Public

RECEIVED
STATE CORPORATION COMMISSION
SEP - 2 1980
CONSERVATION DIV.
Wichita, Kans.