


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
 508 East Murdock, Wichita, Kansas

Company- **IMPERIAL OIL CO.**
 Farm- **Albin** No. **1**

SEC. **31** T. **11** R. **22W**
 NE SW SW

Total Depth. **3895'**
 Comm. **10-21-61** Comp. **10-30-61**
 Shot or Treated.
 Contractor.
 Issued. **1-27-62**

County **Trego** **KANSAS**



Elevation. **2397'** KB

CASING:

8 5/8" 191' cem w/150 sx.

Production. **Dry**

Figures Indicate Bottom of Formations.

surface clay & rocks	191
shale	840
shale & sand	1340
Dakota sand	1560
shale & shells	1625
shale - red bed	1837
Anhydrite	1873
shale & shells	2050
shale & lime	3570
lime	3895 RTD
Total Depth	

TOPS:

Anhydrite (scout)	1837
Heebner	3610
Toronto	3631
Lansing	3644
Base Kansas City	3886

DST #1 3672-97', op 30 mins, rec. 5' drilling mud. IBHP 950#, IFP 0#, FFP 0#, FBHP 0#/20 mins.

DST #2 3696-3711', op 30 mins, rec. 15' drilling mud. IBHP 750#, IFP 0#, FFP 0#, FBHP 665#/20 mins.

DST #3 3715-28', op 30 mins, rec. 5' drilling mud w/scum of oil. IBHP 150#, IFP 0#, FFP 0#, FBHP 0#/20 mins.

DST #4 3726-42', op 1 hr, rec. 630' salt water. IBHP 815#, IFP 50#, FFP 305#, FBHP 800#/20 mins.

DST #5 3772-3895', op 30 mins. Rec. 45' drilling mud. IBHP 110#, IFP 0#, FFP 0#, FBHP 0#/20 mins.