

Operator: A. Scott Ritchie
 Well No.: 3
 Lease Name: Spena "B"
 DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: dry hole

s 21 T11S R 22 W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
DST #1 3592' - 3654' Rec. 400' muddy water. IFP 115-138#/30"; ISIP 1174#/30"; FFP 207-253#/45"; FSIP 1174#/45".				
DST #2 3681' - 3735' Weak blow 9 minutes and died. Rec. 5' mud, no show of oil. IFP 69-69#/15"; ISIP 253#/15"; FFP 92-92#/30"; FSIP 253#/30".				
DST #3 3782' - 3851' Rec. 15' mud, no show of oil. IFP 138#/30"; ISIP 138#/30"; FFP 138#/30"; FSIP 138#/30".				
DST #4 3848' - 3950' Rec. 15' mud. IFP 138-138#/30"; ISIP 207#/30"; FFP 138-138#/30"; FSIP 161#/30".				
			SAMPLE TOPS	
			Anh	1841' (+ 566)
			B/Anh	1889' (+ 518)
			Top	3402' (- 995)
			Heeb	3616' (-1209)
			Tor	3639' (-1232)
			Lans	3654' (-1247)
			B/Kc	3898' (-1491)
			RTD	3950' (-1543)

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received: _____
 Signature: *F. J. Gibson*
 Title: Geologist
 Date: May 22, 1979

06556