

CONTRACTOR'S WELL LOG

State Geological Survey
WICHITA, BRANCH

OPERATOR: Foxfire Exploration, Inc.
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: FLAGLER #3
 LOCATION: C NE NW NE, Section 33-11S-22W
 Trego County, Kansas
 SPUD DATE: 2/17/81
 COMPLETION DATE: 2/26/81

0	305	Clay & Sand
305	1324	Sand & Shale
1324	1541	Cedar Hill Sand
1541	1793	Shale
1793	1836	Anhydrite
1836	3507	Shale
3507	3645	Lime & Shale
3645	3660	Lime
3660	3707	Lime & Chert
3707	3828	Lime & Shale
3828	3916	Lime
3916	3976	Lime & Chert
3976	4007	Lime & Shale
4007	4055	Lime, Shale & Chert
	4055	Rotary Total Depth

Spud hole @ 9:45 a.m., 2/17/81. Drilled 305' of a 12¼" hole. Ran 10 jts. of 8 5/8" - 24# casing (tally 303.87) Set @ 301' K.B. Cemented with 190 sx. of common 2% gel, 3% c.c. Cement did circulate. Plug was down @ 5:30 p.m., 2/17/81.

RTD @ 4055'. ELTD 4056'. Ran 103 jts. of 4½" - 10½# casing (tally 4096.47') Set @ 4055.50'. Cemented with 200 sx. of common 2% gel. Float held. Completed @ 8:15 a.m., 2/26/81.

SAMPLE TOPS:

Hydrite 1793'
 Anhydrite 1836'

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Jack L. Partridge, Vice President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the FLAGLER #3, C NE NW NW, Section 33-11S-22W, Trego County, Kansas.

ABERCROMBIE DRILLING, INC.

BY: Jack L. Partridge
 Jack L. Partridge, Vice President