

PI

34-11-22W

State Geological Survey
WICHITA BRANCH

CONTRACTOR'S WELL LOG

OPERATOR: Foxfire Exploration, Inc.
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: HONAS "B" #1
 LOCATION: NW NW NW, Section 34-11S-22W
 Trego County, Kansas
 SPUD DATE: 5/31/81
 COMPLETION DATE: 6/07/81

0	170	Shale & Sand
170	1800	Sand & Shale
1800	1814	Shale
1814	1857	Anhydrite
1857	3250	Shale
3250	3510	Shale & Lime
3510	3840	Shale
3840	3870	Lime & Shale
3870	3979	Shale & Lime
3979	4063	Lime
	4063	Rotary Total Depth

Spud @ 9:00 p.m., 5/31/81. Drilled 321' of a 12½" hole. Ran 7 joints of 8 5/8" - 20# casing (tally 313.75) Set @ 319' K.B. Cemented with 225 sacks of common 2% gel, 3% c.c. Pumped the p to 304' K.B. Cement did circulate. Plug down @ 3:30 a.m., 6/01/81.

RTD @ 4063'. Ran 105 joints of 4½" - 10½# casing (tally 4081.84) Set @ 4061' K.B. Cemented with 200 sacks of RFC. Cement by Dowell. Plug @ 4050' K.B. Plug down @ 4:00 p.m., 6/07/81.

SAMPLE TOPS:

Anhydrite 1814'
 B/Anhydrite 1857'

RECEIVED
 STATE CORPORATION COMMISSION

JUN 15 1981