

OPERATOR: Zenith Drilling Corporation
CONTRACTOR: Abercrombie Drilling, Inc.
WELL NAME: SCHABEN #1
LOCATION: C NE NE SW, Section 3-11S-23W
Trego County, Kansas
SPUD DATE: 4/07/81
COMPLETION DATE: 4/14/81

0	210	Sand & Shale
210	702	Shale
702	1290	Sand & Shale
1290	1520	Ceder Hills Sand
1520	1787	Shale
1787	1815	Anhydrite
1815	3473	Shale
3473	3940	Lime & Shale
	3940	Rotary Total Depth

Spud @ 2:00 p.m., 4/07/81. Drilled 210' of a 12 $\frac{1}{4}$ " hole. Ran 5 jts. of 8 5/8" - 20# casing (tally 199.78) Set @ 206.79. Cemented with 150 sacks of common 2% gel, 3% c.c. Cement
i circulate. Plug was down @ 6:50 p.m., 4/07/81.

RTD @ 3940'. Set 1st Plug @ 900' with 60 sacks. 50-50 posmix, 6% gel. Set 2nd Plug @ 220' with 30 sacks, 50-50 posmix, 6% gel. Set 3rd Plug @ 40' to surface solid bridge with 10 sacks, 50-50 posmix, 6% gel. 5 sacks in rathole. Job was completed @ 12:45 p.m., 4/14/81. State Plugger - Gilbert Balthazar.

SAMPLE TOPS:

Anhydrite 1783'
Anhydrite 1815'

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Jack L. Partridge, Vice President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the SCHABEN #1, C NE NE SW, Section 3-11S-23W, Trego County, Kansas.

ABERCROMBIE DRILLING, INC.

BY: *Jack L. Partridge*
Jack L. Partridge, Vice President

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state
this 20th day of April, 1981.