


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- WALTERS DRILLING CO., INC.
Farm- Walker **No. 1**

SEC. 6 **T.** 11 **R.** 23W
 SW SW SW

Total Depth. 4395'
Comm. 4-16-54 **Comp.** 4-30-54
Shot or Treated.
Contractor. Walters Drlg. Co., Inc.
Issued. 6-12-54

County Trego **KANSAS**



CASING:
 8 5/8" 196' cem w/100 sx

Elevation. 2294' DF

Production. Dry

Figures Indicate Bottom of Formations.

surface	196
shale, shells & sand	625
shale & shells	874
sand & shale	960
shale & shells	1023
shale & sand	1380
sand	1592
shale & shells	1726
shale & red bed	1885
anhydrite	1933
shale & shells	2438
shale & lime shells	2528
lime	2560
lime & shale	3271
shale & shells	3325
lime	3625
lime & shale	4136
shale	4176
lime & shale	4238
lime	4279
lime, shale & chert	4344
lime & shale	4395
Total Depth	

Tops:

Anhydrite	1885
Topeka	3399
Heebner	3624
Toronto	3644
Lansing-Kansas City	3660
Base Kansas City	3896
Chert Conglomerate	4183
Mississippi	4197
Viola	4261
Simpson	4361
Arbuckle	4372