

AUG 15 1970

elev. 2263 KB

Dry/Penn

DRILLER'S LOG

COMPANY: Halliburton Oil Producing Co., 2915 Classen Blvd.
Oklahoma City, Okla. 73106

CONTRACTOR: Hellar Drilling Company, Inc., Wichita, Kansas 67202

LEASE: #1 Walker

LOCATION: SW NE SW 7-11S-23W, Trego County, Kansas

COMMENCED: July 20, 1970

COMPLETED: July 28, 1970

SING: Set 8 5/8" Surface Casing @ 209'/175 sacks cement

0-34	Sand
34-47	Post Rock
47-209	Shale - Sand
209-455	Chalk - shale
455-595	Shale
595-1849	Shale & Sand
1849-1850	Shale
1850-1892	Anhydrite
1892-2170	Red Bed & Shale & Shells
2170-2395	Shale & Shells
2395-3385	Lime & shale
3385-3485	Lime
3485-3573	Lime & Chert
3573-3640	Lime
3640-3670	Lime (L.K.C.)
3670-3870	Lime
3870	Rotary Total Depth

Anhydrite 1842
1885
Base " 3590
Heebner 3614
Toronto 3637
Lansing 3862
B. K. C.

D & A

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

I, D. L. Hellar, do hereby certify that the above and foregoing is a true and correct copy of the log of the #1-Walker, located in SW NE SW 7-11S-23W, Trego County, Kansas, as reflected by the files of the Hellar Drilling Company, Inc.

HELLAR DRILLING COMPANY, INC.

(Handwritten signature)