

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas


Company-IMPERIAL DRILLING CO., INC.
Farrin-Erickson No. 2

SEC. 9 T. 11 R.23W
C S/2 NW NE

Total Depth. 3762
Comm. 10-17-54 Comp. 10-26-54
Shot or Treated.
Contractor. Imperial Drilling Co., Inc.
Issued. 12-25-54

County Trego

KANSAS



Elevation. 2277 RB

Production. 997 BOPD, no wtr

CASING:

8 5/8 @ 214' w/ 150 sx cmt.
5 1/2 @ 3762' w/ 125 sx cmt.

Figures Indicate Bottom of Formations.

gravel & shells	190
sand & shale	560
shale, shells & sand	1180
shale & shells	1270
Dakota sand	1500
shale & shells	1751
anhydrite	1792
shale & shells	2590
lime & shale	3500
lime	3762
Total Depth	

TOPS:

Anhydrite	1751
Heebner	3474
Lansing	3508

DST #1: 3521-37, open 1 hr. weak blow
12 min. rec. 6' mud, BHP 0#, SI 20 min.

DST #2: 3535-51, open 1 hr. gas to
surf. 40 min. rec. 450' clean oil,
550' GC muddy oil, IFP 35#, FFP 310#
BHP 835#, SI 20 min.

DST #3: 3558-74, open 1 hr. weak steady
blow, rec. 50' gas, 25' OCM, BHP 500#
still building up in 20 min.

DST #4: 3609-16, open 1 hr, strong
blow, rec. 750' gas, 25' muddy oil, 30'
free oil, FFP 35#, BHP 800#, SI 20 min.