


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- ICER ADDIS
Farm- Galloway No. 1

SEC. 10 T. 11 R. 23W
SW NE SW

Total Depth. 3750'
Comm. 8-2-58 Comp. 8-12-58
Shot or Treated.
Contractor. Triangle Drlg., Inc.
Issued. 1-3-59

County Trego
KANSAS



Elevation. 2265' KB

Production. Dry

CASING:

8 5/8" 217' cem w/175 sx.

Figures Indicate Bottom of Formations.

surface clay	10
sandstone	70
shale & limestone	100
shale, clay, sandstone streaks	200
blue shale & clay	217
shale and shells	760
sandstone	875
shale and sandstone	995
sandstone	1060
shale and red bed	1195
sandstone	1420
sandstone and shale	1480
red bed	1734
Anhydrite	1775
shale, shells, sandstone	1910
shale and shells	2310
sandy limestone & shale	2410
limestone & shale	3244
limestone	3738
shale	3750 RTD
Total Depth	

TOPS:

Anhydrite (Drillers)	1734
Topeka	3244
Heebner	3478
Toronto	3498
Lansing	3513
Base Kansas City	3738