

ALMA PETROLEUM CO & R. MCNEELEY  
 Rhoades Estate No. 1.

SEC. 14 T. 11 R. 23 W.  
 C SW SW

SEP 29 1934

Plotted Texas CO.


County. Trego.

Total Depth. 4222  
 Comm. 4-6-34 Comp. 8-29-34  
 Shot or Treated. 2000 gal acid.  
 Contractor. Rose Spring Drilling Co.  
 Issued. 9-29-34.

Rotary to 3593

CASING.

15 1/2" 124' 8 1/2" 3555'  
 6" 3700' UR 3860



Elevation. 2301

Production. 120 B. some wtr.  
 Potential 346 B.

Figures Indicate Bottom of Formations

shale	315	shale	3245
shale and lime	440	broken lime	3295
shale and shells	810	shale	3311
sand	878	lime	3330
shale and shells	1020	broken lime	3360
sand	1100	lime	3490
shale and shells	1150	lime	3603
shale and red rock	1170	shale	3605
shale	1220	show oil 3578-92	
sand	1250	show oil 3619-20 10 bbls per day.	
shale	1285	lime	3620
sand	1350	show oil 3619-20 10 BOPH HF 3620-24	
sand	1460	sand	3625
sdv shale	1480	HFV 3622	
sand	1515	lime	3632
shale and red rock	1531	shale	3636
sdv shale	1550	sdv lime	3652
shale and red rock	1575	lime	3682
shale	1610	shale	3700
shale and red rock	1645	lime	3716
no log	1745	shale green	3721
lime	1800	lime	3727
shale and shells	1830	red rock	3733
shale	1865	lime	3743
shale and red rock	1965	shale	3756
sdv shale	1990	lime	3763
sdv shale	2065	red rock	3775
shale and shells	2115	lime	3825
shale and red rock	2140	lime	3832
shale	2340	Var. col shale	3853
shale and shells	2370	red rock	3860
sdv shale	2380	lime	3870
shale and shells	2395	red rock, shells, chert and	
shale	2400	sand	3877
lime	2405	red rock and shells	3915
shale	2460	HFV 3887-3915.	
lime	2470	show oil 3910-15	
shale and shells	2560	lime and chat	3930
shale	2590	lime	3940
shale and lime	2600	shale and green	3955
shale	2630	conglomerate	3978
lime	2695	lime	4020
lime and shale	2750	lime	4025
lime	2810	red rock	4026
lime and shale	2815	lime	4070
broken lime	2845	1 BW 4040-50	
lime	2900	sand	4080
broken lime	2945	2 BW 4070-80	
lime	2980	lime	4100
lime	3005	HFV 4096	
broken lime	3030	lime	4105
lime	3090	lime	4200
shale	3140	lime	4222
lime	3160	P.B. to 3627 TD.	
shale	3165	swab 150 B. fluid per day.	
lime	3205	est 30 B. 240 B. water and 50 BO per day.	
broken lime	3225	inc water. Pay 3560-3620 wtr 3636	