


Plotted Texas Co. Plotted

ALMA OIL CO.
Rhoades No. 2.

SEC. 14 T.11 R.23W
c NW NE
660' fr WL
660' fr NL
660' fr EL NW NE
County. Trego.

Total Depth. 3563' 6"
Comm. 12-11-35 Comp. 12-29-35
Shot or Treated.
Contractor.
Issued. 7-11-36
Casing:
12 1/2" 118'
7" O.D. 3450'



Elevation.

Production. Est. 70

Figures Indicate Bottom of Formations. B.Oil, 40 Water

sand & clay	118	shale & broken lime	3054
shale	270	shale & shells	3100
shale & shells	540	broken lime	3300
shale	765	shale & shells	3352
lime	850	broken lime	3400
shale shells	950	lime	3440
sand	970	coring	3445
lime	1071	shale red coloring	3450
shale & shells	1170	coring	3452
sand	1450	S.L.M. 3450	
sandy lime	1480	(Bottom Rotary hole 3450')	
red bed & shale	1705	lime hard	3474
lime	1740	shale	3502
anhydrite & shale	1775	lime	3508
anhydrite	1800	lime soft	3516
broken lime	1854	lime hard	3519
shale	1940	shale	3525
shale & shells	2000	lime	3541
broken lime	2037	water sand	3548
shale	2185	lime	3562
shale shells & lime	2223	shale	3563 6"
broken lime	2290	Total Depth	
lime	2320		
shale & shells	2360		
broken lime & shale	2430		
broken lime	2475		
lime	2565		
lime white	2600		
shale	2630		
shale & shells	2665		
broken lime	2720		
sandy shale	2755		
broken lime	2780		
lime	2900		
shale	2930		
lime grey	2961		
lime shells & shale	3006		