


WATCHORN OIL & GAS CO.
Lemko No. 2A.

SEC. 15 T. 11 R. 23W
SE NE SW
330' W 330' N SE NE SW

Total Depth. 3975'
Comm. 4-11-37 Comp. 7-23-37
Shot or Treated.
Contractor.
Issued. 11-20-37

County. Trego

NOV 20 1937



CASING:

10 3/4" 100'
7" 3476'
5 3/16" 3814' P

Elevation.

Production.

Dry

Figures Indicate Bottom of Formations.

surface	100	shale	3746
shale	385	limo	3773
shale & shells	710	shale	3798
shale	770	lime	3800
lime sdy	830	red rock	3813
brkn limo	855	lime	3828
shale & lime	960	brkn limo	3835
sand	1000	lime	3839
limo	1037	brkn limo	3850
shale, limo	1140	lime	3870
red bed	1150	shale	3875
red bed & sand	1370	limo	3900
sand	1400	brkn lime	3925
shale	1485	lime	3935
red bed	1680	conglomerate	3960
red bed-shale	1717	lime	3962
anhydrite	1755	Top Siliceous limo	3962
lime shells & shale	1780	Siliceous limo	3975
shale & red bed	1960	Total Depth.	
shale & lime	2020		
shale & lime shells	2141	9BWPB 3962-3970	
shale	2195		
shale & lime	2238		
brkn lime	2275		
lime	2369		
shale	2405		
lime & shale	2563		
brkn lime	2590		
lime & shale	2673		
shale	2710		
brkn lime	2776		
lime	2845		
brkn lime	2939		
lime & shale	2992		
brkn lime	3090		
lime & shale	3320		
brkn lime	3340		
sdv lime	3357		
brkn lime	3384		
lime(hole corr. 22')	3450		

SIM 3472

Coring 3472-3489

Top K.C. lime 3480

lime	3492
lime 9BWPB	3494
lime	3510
lime	3524
shale blk	3529
lime	3555
lime grey	3571
shale	3584
brkn lime	3587
lime	3596
shale	3607
lime white	3612
brkn lime	3627
shale	3644
lime	3691
brkn lime	3715
lime	3725