

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.  
412 Union National Bank Bldg., Wichita, Kansas

PLOTTED  
P. E. Jameson  
Plotted Texas CO.


WATCHORN OIL & GAS CO.  
Wilson No. 1.

SEC. 22 T. 11 R. 23W.  
NW NE NW  
330' E. 330' S.

Total Depth. 3501  
Comm. 5-7-37 Comp. 6-6-37  
Shot or Treated. 5000 gal acid.  
Contractor.  
Issued. 9-18-37

SEP 18 1937

County Trego.



CASING.

103/4" 100' 7" 3482'

Elevation.

Production. Pot. 400 B.

Figures Indicate Bottom of Formations.

surface soil	24
gravel	27
shale and shells	670
sand	720
shale and lime	880
shale and shells	950
sand and shale	1090
red bed and shale	1130
lime and red bed	1200
sand and red bed	1490
shale and red bed	1735
anhydrite	1758
anhydrite and shale	1834
shale and red bed	1967
shale	2050
lime and shale	2294
lime broken	2425
broken lime	2954
shale and lime	3073
shale and lime shells	3149
shale and lime	3215
broken lime	3360
lime	3487
coring(14' Recovery	3501
line	3501
Total Depth.	