

Albert Wheeler

Plotted Texas CO.


CONTINENTAL OIL CO.
J.H. Carpenter No. 1.

SEC. 23 T. 11 R. 23W
C NW NW
660'S 660'E of NW Cor.

Total Depth, 3777' P.B. 2625'
Comm. 5-27-36 Comp. 9-9-36
Shot or Treated. 2000 Gals. Acid 8-29-36
Contractor.
Issued. 10-10-36

County. Trego

OCT 10 1936



CASING:

16" 55'
10 3/4" 1100'
7" 3543'

Production. 10 B. Oil
125 BW

Figures Indicate Bottom of Formations.

surface	78	lime	3657
shale & shells	114	brkn lime	3664
sand & shale	265	lime	3670
shale & shells	674	shale	3675
brkn sand	905	lime	3682
sand shells & shale	1100	shale	3688
sdv shale	1265	lime	3693
shale red & sand	1302	3693 equals 3703 Corr.	
sand	1512	lime	3703-3705
shale & sand	1740	brkn lime	3714
shale red	1770	lime	3722
anhydrite	1826	brkn lime & shale	3728
shale red & sdv		brkn lime	3739
shale	1910	lime	3744
sdv shale	2039	red rock	3745
shale & shells	2222	brkn lime & shale	3755
shale	2315	lime	3757
lime & shale	2355	show of oil 3755-3757	
lime & gypsum	2477	lime	3761
lime	2508	brkn lime & shale	3772
sand	2512	lime	3777
lime	2520	Total Depth.	
brkn lime	2624	Plugged Back to 3635'	
lime	2648	7 Bbls. Oil & 1 1/2 BW before Acid,	
brkn lime	2718	10 Bbls. Oil & 125 BW after Acid.	
lime	2769	Plugged Back to 2625' Shut Down	
brkn lime	2972	Geological Tops:	
lime	3006	Top Anhydrite 1740'	
brkn lime	3037	Top Nova 2830'	
lime	3087	Top Kansas City 3540'	
lime & shale	3149		
brkn lime	3280		
brkn lime & gypsum	3345		
lime	3378		
brkn lime	3529		
lime RUST 3545	3563		
shale	3565		
lime	3583		
shale	3587		
lime	3598		

3 bbls oil & water
por hour 3395

shale red & blue	3602
lime	3609
sdv shale	3613
lime	3615
sdv shale	3617
25 bbls water & 10 B.	
Oil per day 3615.	
lime brown	3619
brkn lime	3622
lime	3623
brkn lime	3626
lime	3628
shale	3632
lime	3640
brkn lime	3652