

*Plotted
Lee Norcross*

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bldg., Wichita, Kansas.

Plotted Texas CO.


CONTINENTAL OIL CO.
Holcomb No. 1-A

SEC. 26 T. 11 R. 23W
CWL NE $\frac{1}{4}$
440' E 1320' S North 1/4 Cor.

Total Depth. 3681' P.B.3675'
Comm. 4-21-36 Comp. 7-7-36
Shot or Treated. 4000 Gals.
Contractor. C. M. Murray, Tulsa.
Issued. 9-12-36

County. Trego

SEP 12 1936



Elevation.

Production. 495 B.

CASING:

15 $\frac{1}{2}$ "	45'3"
10	1142'8"
7	8638'1"
5 $\frac{1}{2}$ Liner	61'10"

Figures Indicate Bottom of Formations.

shale	60	brown lime	3212
surface sand	72	brkn lime	3245
shale	170	shale & lime	3311
shale & lime shells	404	lime & sdy shale	3415
sdv shale	747	sdv lime	3442
sand soft	812	lime hrd	3471
brkn sand (hrd & sft)	880	brkn lime	3500
Dakota sand	920	lime	3510
anhydrite hrd	956	brkn lime	3562
sdv shale & Dak. sand	1140	lime & shale	3589
Acid test at 1000'		brkn lime	3615
red rock & lime shells	1217	lime	3641
sdv shale	1242	K.C.lime firm	3648
sand sft	1562	Cleaned out from 3579-3615.	
red rock	1600	5' cavings in hole.	
shale & red bed	1700	1200' of oil in hole at 3661	
red bed & gyp	1793	shale blk sft	3654
red gummy clay & anh.	1831	blue brown green shale	3660
anhydrite	1910	lime	3671
brkn anhydrite	1948	lime brown	3674
red bed	1955	lime hrd	3675
anhydrite	1962	cherty limo	3681
red bed & anhydrite	2021	Total Depth.	
anhydrite	2068		
red bed & anhydrite	2101	Plugged Back 3675'	
red bed & shale	2154		
red bed & shells	2209	Geological Tops.	
red bed sand streak	2280		
red bed & lime	2307	Top of Neva 2890'	
red bed & gyp	2355	Top of Kansas City 3610'	
shale & lime	2425		
lime & gyp	2774		
brkn lime	2844		
lime & shale	2943		
brkn lime	2970		
lime & shale	3074		
lime	3107		
shale & lime	3170		
sdv lime	3205		