


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - LAUCK & MONCRIEF
Farm - Howat No. 1.

SEC. 26 T. 11 R. 23 W
NW NE NW

Total Depth. 4152 Corr. DF
Comm. 6-16-45 Comp. 7-18-45
Shot or Treated.
Contractor.
Issued. 8-4-45

County. Trego
KANSAS



CASING:
10" 157' Cem.
5" 4086' Cem.

Elevation. _____

Production. Dry

Figures Indicate Bottom of Formations.

surface	30
sand	35
shale & shells	775
sand	800
shale & shells	870
lime	960
shale, shells, sand	1250
shale	1307
sand	1600
lime	1690
shale	2415
shale & lime	2697
shale & shells	2730
lime	2822
shale & lime	2835
lime	2883
shale & lime	2916
lime	3035
shale & lime	3232
lime	3340
shale & lime	3385
lime	3695
lime & chert	3715
lime	3882
shale	3905
shale & lime	3968
shale	3990
shale & chert	4000
shale & lime	4045
conglomerate	4133
Arbuckle lime	4141
Total Depth	

Above Measurements uncorrected-
correct down 12 feet from 2250

Tops Corr. DF

Neva	2922
Topeka	3397
Lansing	3637

show oil 3738-41

show oil 3749-56

show oil 4053-65

Conglomerate	4087
Arbuckle	4144
Total Depth	4152

Plug 4074
Perforate 4053-67/58 shots,
show oil;
Acidized 1000 gals. 10 gals
oil per hr.
Plug 3778
Perforate 3737-42/28 shots
show oil. 3749-57/24 shots
Acidized 1000 gals.
water - trace of oil.
Dry & abandoned