


KANSAS GEOLOGICAL SOCIETY
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

COMPANY MC CLURE OIL
 FARM Mary Weber NO. 1

SEC. 2 T. 11 R. 24W
 LOC. C SE NE

TOTAL DEPTH 3943'
 COMM. 8-7-67 COMP. 8-15-67
 SHOT OR TREATED
 CONTRACTOR Abercrombie Drilling
 ISSUED 9-16-67

COUNTY Trego



CASING
 20 10
 15 XXX 7" 202' cem w/ 100 sx
 12 6
 13 5

ELEVATION 2338' KB

PRODUCTION Dry/ Base Kansas
 City

FIGURES INDICATE BOTTOM OF FORMATIONS

| | | |
|------|------|---------------------------------|
| 0 | 70 | Surface Sand |
| 70 | 230 | Shale |
| 230 | 1225 | Shale - Sand w/pyrite streaks ✓ |
| 1225 | 1468 | Shale & Sand |
| 1468 | 1690 | Sand |
| 1690 | 1942 | Red Bed |
| 1942 | 1978 | Anhydrite |
| 1978 | 2640 | Shale with Shells |
| 2640 | 3532 | Shale & Lime |
| 3532 | 3702 | Lime |
| 3702 | 3755 | Lime & Chert |
| 3755 | 3940 | Lime |
| | 3940 | Rotary Total Depth |
| | 3943 | Total Depth |

ELECTRIC LOG TOPS:

| | | | |
|-----------|------|---------|------|
| Anhydrite | 1935 | (+ 403) | |
| Heebner | 3663 | (-1325) | 3663 |
| Toronto | 3684 | (-1346) | 3684 |
| Lansing | 3697 | (-1359) | 3697 |
| B/K.C. | 3932 | (-1594) | 3932 |
| R.T.D. | 3940 | (-1602) | |
| E.L.T.D. | 3943 | (-1605) | |

Smp Tops ELEVATION: 2338 K. B.
 2337 D. F.
 2331 G. L.



STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, A. L. Abercrombie, do hereby certify that the above and foregoing is a true and correct copy of the files of Abercrombie Drilling, Inc. on the Mary Weber #1, C SE NE of Section 2-11S-24W, Trego County, Kansas.

A. L. Abercrombie
 A. L. Abercrombie
 President

Subscribed and sworn to me, a Notary Public, in and for Sedgwick County, Kansas, on the seventeenth day of August 1967