

PT
CHIEF DRILLING CO., Inc.

Drilling Contractors - Oil Producers

SUITE 905 CENTURY PLAZA

WICHITA, KANSAS 67202

V. RICHARD HOOVER
PRESIDENT

DAILY DRILLING REPORT

RIG #1

(316) 262-3791

BERG #1 (#2261 Farmout Gear)
W/2 E/2 SE/4 6-11S-24W
Trego County, Kansas

ELEVATION: 2365 Gr.
2367 D.F.
2370 K.B.

5-23-84 Moving in on location
5-24-84 Finished moving in, Spudded in
@ 3:15 p.m. Ran 7 jts. new 20#
8 5/8" 296' set @ 299' gr., cem.
w/200 sx. of 60-40 posmix, 3%
c.c., 2% gel, plug down 8:00 pm.
5-25-84 Drilling @ 475'
5-26-84 Drilling @ 2079'
5-27-84 Drilling @ 2890'
5-28-84 Drilling @ 3500'
5-29-84 DST #1 3683 - 3714 Toronto 30-
30-30-30 wk. blow died in 30 min.,
Rec. 20' mud, IBHP: 1230#, FBHP:
1200#, FP: 70-70 DST #2 3735 -
3755 35' zone, wk. blow died in
23", 30-30-30-30, Rec. 26' mud,
IBHP: 1250#, FBHP: 1250#, IFP:
60#, FFP: 70#, Drilling ahead,
DST #3 3776 - 3810 70 & 90 zone
30-30-30-30 st. blow, rec. 2500'
muddy salt water, IBHP: 1290#,
FBHP: 1290#, IFP: 850 FFP: 1200
5-30-84 DST #4 3843 - 3863 Lansing 140
30-30-30-30 strong blow, rec.
2050' muddy salt water, IBHP:
1375#, FBHP: 1350#, IFP: 890 FFP:
1240
5-31-84 DST #5 3865 - 3885 Lans. 160 zone
30-30-75-30 strong blow, Rec. 62'
oil & water cut mud (20% G, 7% O,
3% W, 70% M) 62' oil & gas cut
watery mud, (40% G, 7% O, 11% W,
42% M) 434' muddy water, IBHP: 730#
FBHP: 700#, IFP: 135 FFP: 275
DST #6 3893 - 3905 (Lans. 180 zone)
30-30-30-30 strong blow in 3 min.
Rec. 1020' muddy salt water, IBHP:
695#, FBHP: 695#, IFP: 340#, FFP: 500#
6-01-84 DST #7 3908 - 3925 (Lans. 200' zone)
30-30-60-45 wk. blow bldg to fair, Rec.
50' watery mud, w/few oil spots, IBHP:
800#, FBHP: 600#, FP: 80-80 RTD 3960'
D & A, Plugged w/195 sx. 50-50 posmix, 6% gel, 3% c.c.
1st plug @ 2010' w/25 sx., 2nd plug @ 1050' w/100 sx.,
plus 1 sx. flow seal, 50 sx. @ 300', solid bridge @ 40'
w/10 sx., 10 sx. in rat hole, Plug down @ 8:00 p.m.
District #6 Marion Schmidt State Plugger

FORMATION TOPS:

Anhydrite	1993	+	377
Base Anhydr.	2033	+	337
Heebner	3676	-	1306
Lansing	3716	-	1346
Muncie Cr.	3838	-	1468
Stark	3908	-	1538
Hush Puckney	3926	-	1556
BKC	3949	-	1579
RTD	3960	-	1590

JUN 11 1984

State Geological Survey
WICHITA BRANCH

RECEIVED
STATE CORPORATION COMMISSION

JUN 07 1984

CONSERVATION DIVISION
Wichita, Kansas