

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company MAZDA OIL CORP.
Farm Central Life No. 1

SEC. 16 T. 11 R. 24W
SEc NE

Total Depth. 4573

Comm. 8-19-46


Shot or Treated.

Contractor.

issued. 9-28-46

Comp. 9-8-46

County. Trego KANSAS



Elevation. 2434

Production. Dry

Figures Indicate Bottom of Formations.

surface clay	10
rock	30
shale & shells	400
shale	525
shale blue & black	925
sand, shale & iron streaks	1220
shale blue, iron	1275
water sand	1305
shale, shells & red bed	1500
shale & red bed	1575
sand, shale & red bed	1740
shale & red bed	1975
shale	2035
Anhydrite	2075
shale & shells	2200
red bed, shale & shells	2485
salt, shale & shells	2580
lime & shale	2690
red rock, shale & shells	2730
shale & sdy lime	2895
lime & shale	3240
lime, shale, St. of Pyrite	3300
lime & shale	3405
lime brkn & shale.	3485
lime & shale	3550
lime	3882
lime & chert	3905
lime	4047
shale & lime	4185
lime & Chert	4206
lime & shale	4285
lime, shale-Cong.	4326
shale, lim & chert	4339
lime & chert	4353
Chert	4392
Cherty Limo	4396
lime	4435
Cherty Limo	4475
lime	4520
cherty lime	4543
Arbuckle	4573
Total Depth	

Tops:

Topeka	3538
Lansing K. C.	3788
Base K. C.	4034
Conglomerate	4259
Mississippi	4339
Miss. Dolomite	4435
Arbuckle	4543