

CONFIDENTIAL

CONFIDENTIAL

KANSAS DRILLERS LOG

CONFIDENTIAL

JUN 8 0 RECD

State Geological Survey
WICHITA BRANCH


Released
7/16/81

S. 18 T. 11S R. 24 E W

Loc. SE SW NE

County Trego

640 Acres



Elev.: Gr. 2415'

DF _____ KB 2420'

API No. 15 — 195 — 20,658
County Number

Operator
RUPE OIL COMPANY, INC.

Address P. O. Box 2273
Wichita, Kansas 67201

Well No. 1 Lease Name Dale Hillman

Footage Location
2310 feet from (N) X522line 1650 feet from (E) 0004 line

Principal Contractor Warrior Drilling, Inc. Geologist Martha Tetrick Kopper

Spud Date June 9, 1980 Total Depth 4011' P.B.T.D.

Date Completed June 18, 1980 Oil Purchaser

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface		8-5/8"	28#	253'	Common	150	3% Calcium Chloride 2% Gell

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
RATE OF PRODUCTION PER 24 HOURS	Oil bbls.	Gas MCF	Water bbls.	Gas-oil ratio	CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval(s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on an open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator RUPE OIL COMPANY, Inc.		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: Dry Hole
Well No. 1	Lease Name Dale Hillman	
S 18 T 11S R 24 W		

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
<u>DST #1 3787'-3822'</u> - 45"-30"-30"-30" Weak blow; Recovered 40' oil specked mud. ISIP 599#; IFP 43-43#; FSIP 588#; FFP 54-54#.			Anhydrite	2020'
			Topeka	3503'
<u>DST #2 3896'-3940'</u> - 30"-30"-12"-30" Very weak blow, died on 2nd opening; Recovered 10' mud; ISIP 349#; IFP 43-43#; FSIP 426#, FFP 43-54#.			Heebner	3723'
			Lansing	3758'
			Bse. Kansas City	3998'
<u>DST #3 3944'-3970'</u> - 30"-45"-60"-60" Fair blow. Recovered 114' gas in pipe; 5' free oil; 5' mud cut oil (slightly gas cut); 10' slightly gas cut mud; 52' muddy cut gassy water; 62' gas cut water; 180' salt water. ISIP 1115#; IFP 54-98#; FSIP 1083#; FFP 120-174#.				
<u>DST #4 3965'-4011'</u> - 30"-45"-60"-60" Fair blow; recovered 278' salt water. ISIP 825#; IFP 43-65#; FSIP 750#; FFP 98-141#.				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	RUPE OIL COMPANY, INC.
	By: <u>Martha Tetrick Kopper</u>
	Martha Tetrick Kopper Petroleum Geologist
	Title
	June 23, 1980
	Date

18046