

Operator Name OXFORD EXPLORATION COMPANY Lease Name SCHAUS Well # 2Sec. 23 Twp. 11S Rge. 24 ☐ East ☒ West County Trego

WELL LOG

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all drill stem tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface during test. Attach extra sheet if more space is needed. Attach copy of log.

Drill Stem Tests Taken ☒ Yes ☐ No
 Samples Sent to Geological Survey ☐ Yes ☐ No
 Cores Taken ☐ Yes ☐ No

Formation Description
☐ Log ☒ Sample

	Name	Top	Bottom
DST #1 3818-3836' rec 130' mw; 1BHP 1305#/30", FBHP 1288#/30", FP 37-70#	ANHYDRITE B/ANHYDRITE	2032 2075	(+413) (+370)
DST #2 3928-3972' rec 8' oil cut mud; 1BHP 45#/30" FBHP 22#/30", FP 22-22#	HEEBNER TORONTO	3758 3780	(-1313) (-1335)
DST #3 3968-3972' rec 10' mud; 1BHP 55#/30" FBHP 30#/30", FP 30-30#	LANSING BLK SH TD	3794 3926 3994	(-1349) (-1481) (-1549)

* Well was completed for disposal at 1610-1766'-Casing was set only to 2005'

CASING RECORD ☐ New ☐ Used							
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (in O.D.)	Weight Lbs/Ft.	Setting Depth	Type of Cement	#Sacks Used	Type and Percent Additives
Surface Casing	12 1/2"	8 5/8"	28	206	Common	165	
Production	7 7/8"	5 1/2"	15.5	2005	Common	450	6% gel
PERFORATION RECORD				Acid, Fracture, Shot, Cement Squeeze Record			
Shots Per Foot	Specify Footage of Each Interval Perforated			(Amount and Kind of Material Used)		Depth	
1	1746-1766						
1	1714-1724						
1	1660-1680						
1	1610-1630						
TUBING RECORD		Size 2 3/8"	Set At 1570'	Packer at 1562'	Liner Run	☐ Yes ☒ No	
Date of First Production	Producing Method ☐ Flowing ☐ Pumping ☐ Gas Lift ☐ Other (explain).....						
Estimated Production Per 24 Hours	Oil	Gas	Water	Gas-Oil Ratio	Gravity		
	Bbls	MCF	Bbls	CFPB			

METHOD OF COMPLETION

Production Interval

Disposition of gas: ☐ Vented
☐ Sold
☐ Used on Lease

☐ Open Hole ☐ Perforation
☐ Other (Specify)

☐ Dually Completed
☐ Commingled