

IMPORTANT
Kans. Geo. Survey request
samples on this well.


KANSAS DRILLERS LOG

S. 26 T. 11 R. 24 ^E/_W

Loc. C NL NE

County Trego

640 Acres
N



Elev.: Gr. 2433

DF 2435 KB 2438

API No. 15 — 195 — 20,309
County Number

Operator
Chief Drilling Co., Inc.

Address
905 Century Plaza Wichita, Kansas 67202

Well No. # 1 Lease Name Connor

Footage Location
feet from (N) (S) line feet from (E) (W) line

Principal Contractor Company Tools Geologist Don D. Strong

Spud Date 11/10/74 Total Depth 4045' P.B.T.D.

Date Completed 11/18/74 Oil Purchaser

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
	12 1/4	8 5/8"	28#	209'	quick set	165	
	7 7/8	4 1/2"	10 1/2#	4044'	60/40 pozmix	200	6% gel
					60/40 pozmix	250	
					(Two Stage)		

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2	D-P's	3964-3970
TUBING RECORD			2	D-P's	3946-3952
Size <u>2 3/8"</u>	Setting depth <u>4040'</u>	Packer set at <u>3935'</u>			

O.D.E.U.E.

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
3000 gal. 15% Reg.	Selective 3964-3970 3946-3952

INITIAL PRODUCTION

Date of first production <u>12-15-74</u>	Producing method (flowing, pumping, gas lift, etc.) <u>Pumping</u>
RATE OF PRODUCTION PER 24 HOURS	Oil <u>96</u> bbls. Gas <u>80</u> bbls. Water <u>80</u> bbls. Gas-oil ratio <u>CFPB</u>
Disposition of gas (vented, used on lease or sold)	Producing interval(s)

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator **Chief Drilling Co., Inc.** DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
 Well No. **1** Lease Name **Connor** Oil
 S 26 T 11 R 24 W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries. SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
DST #1 3772-3823' Top & 35' zones Open 2 hours Rec. 1900' Salt water IBHP: 1395#/30" FBHP: 1385#/30" FP: 72-912#	3772	3823	<u>FORMATION TOPS</u>	
			Anhydrite	2025
			Base Anhy.	2064
			Heebner	3743
			Toronto	3766
			Lansing	3779
			R.T.D.	4045
DST #2 160' zone Open 2 hours Rec. 240' gas 185' muddy oil IBHP: 310#/30" FBHP: 306#/45" FP: 35-292#	3936	3955	<u>ELECTRIC LOG TOPS</u>	
			Anhydrite	2022
			Base Anhy.	2063
			Heebner	3743
			Toronto	3766
			Lansing	3779
			B.K.C.	4002
			L.T.D.	4045
DST #3 180' zone Open 2 hours Rec. 600' gas 210' muddy oil IBHP: 1155#/30" FBHP: 370#/30" FP: 48-108#	3959	3984		

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.



Jim Palmer
 Signature
 Vice-President
 Title
 December 27, 1974
 Date

12186

WELL LOG

CHIEF DRILLING CO., INC.
Suite 905 Century Plaza
Wichita, Kansas 67202

#1 CONNOR
C NL NE/4 Sec. 26-11-24W
Trego County, Kansas

CONTRACTOR: Company Tools
CASING RECORD: Set 209' of 8 5/8" w/165
sacks Common Quick Set
Cement; 4044' of 4 1/2" w/200
sacks 60-40 Pozmix 18% salt,
250 sacks common 6% gel &
250 sacks 60-40 Posmix 6% gel

COMMENCED: 11/9/74
COMPLETED: 11/18/74

RECEIVED
STATE CORPORATION COMMISSION
NOV 22 1974
CONSERVATION DIVISION
Wichita, Kansas

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATION</u>
Surface Hole	0	206	2433 Gr.
Shale & Sand	206	1892	2435 D.F.
Shale	1892	3090	2438 K.B.
Shale & Lime	3090	3228	
Shale	3228	3448	
Lime & Shale	3448	3823	
Lime	3823	3840	
Lime & Shale	3840	3914	
Lime	3914	4045	
Total Depth	4045		

ELECTRIC LOG TOPS

Anhydrite	2022 +	416
Base Anhy.	2063 +	375
Heebner	3743 -	1305
Toronto	3766 -	1328
Lansing	3779 -	1341
B.K.C.	4002 -	1564
L.T.D.	4045 -	1607

STATE OF KANSAS, COUNTY OF SEDGWICK) ss:

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the C NL NE/4 of Section 26-11-24W, Trego County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

Jim Robinson

Jim Robinson, Vice President

Subscribed and sworn to before me this 21st day of November, 1974.

Virginia S. Fabian

Virginia S. Fabian, Notary Public

