

COPY

CONTRACTOR'S WELL LOG

OPERATOR:	F & M Oil Company
CONTRACTOR:	Abercrombie Drilling, Inc.
WELL NAME:	WEISBECK #1
LOCATION:	SE SE NW, Section 33-11S-25W Trego County, Kansas
SPUD DATE:	07-11-80
COMPLETION DATE:	07-18-80

0	1908	Sand & Shale
1908	1958	Anhydrite
1958	2653	Sand & Shale
2653	4500	Shale & Lime
	4500	Rotary Total Depth

Spud hole at 10:45 a.m. on 07-11-80. Drilled 260' in a 12-1/4" hole. Ran 6 joints of used 7-5/8" - 28# casing (tally 250.28). Set at 256.78. Cemented with 175 sx. of common, 3% c.c., 2% gel. Plug was down at 7:00 p.m. on 07-11-80.

R.T.D. 4500', L.T.D. 4492'. Set 1st plug at 1000' with 60 sx., 2nd plug at 240' with 30 sx., 3rd plug at 40', solid bridge. Rathole with 5 sx., 50/50 posmix, 6% gel. State plugger was Gilbert Balthazor. Plug was down at 7:15 p.m. 07-18-80.

SAMPLE TOPS:

Anhydrite	2150'
Anhydrite	2180'

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the WEISBECK #1, SE SE NW, Section 33-11S-25W, Trego County, Kansas.

ABERCROMBIE DRILLING, INC.

BY: Jack L. Partridge
Jack L. Partridge, Asst. Sec.-Treas.