


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- JENNINGS, PRIME DRILLING CO. & HUDSON OIL SEC. 11 T. 11 R. 29W  
Farm- Burris No. 1 C SW SW

Total Depth. 4575'  
Comm. 3-29-58 Comp. 4-16-58  
Shot or Treated.  
Contractor. Prime Drilling Co.  
Issued. 5-17-58

County Gove

KANSAS



Elevation. 2849' KB

Production. Dry

CASING:  
8 5/8" 211' cem w/125 sx.

Figures Indicate Bottom of Formations.

surface clay	40
sand	100
sand & shale	118
sand	175
clay & shale	212
shale & shells	1015
sand & shale	1170
shale	1375
shale & shells	1945
Anhydrite	1975
red bed & shale	2040
red bed, shale & shells	2345
shale & shells	2685
shale & lime	2960
lime & shale	3730
lime	3790
lime & shale	3840
lime	4196
lime & shale	4320
lime	4522
Mississippi	4575 RTD
Total Depth	

TOPS:	SAMPLE	ELECTRIC
Anhydrite	1945	
Heebner	3921	3919
Toronto	3945	3942
Lansing	3959	3958
Base of Kansas City	4222	4219
Marmaton	4338	4339
Fort Scott	4423	4425
Mississippian	4522	4520

DRILL STEM TESTS:

#1 4020-41, Misrun (Hole in drill pipe).

#2 4020-41, open 2 hrs., rec. 40' slightly oil cut mud, 180' salt water, BHP 1200#.

#3 4049-70, open 2 hrs., rec. 515' salt water, BHP 1200#.

#4 4342-65, open 1 hr., rec. 15' mud, BHP 0#.