

KANSAS DRILLERS LOG

State Geological Survey

WICHITA BRANCH


API No. 15 — 063 — 20,504
County Number

S. 17 T. 11 R. 31 E. W

Loc. C NW NW

County Gove

640 Acres
N



Locate well correctly

Elev.: Gr. 3011

DF KB 3016

Operator William E. Wise	
Address 46B - DTC 7720 E. Bellevue Ave. - Englewood, Colorado 80111	
Well No. 1	Lease Name Pioneer
Footage Location 660 feet from (N) (S) line 660 feet from (E) (W) line	
Principal Contractor Aldril Exploration	Geologist Karl Buehler
Spud Date June 4, 1981	Total Depth 4708
	P.B.T.D. surface
Date Completed June 19, 1981	Oil Purchaser

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4	8 5/8	20	309	60/40 Pozmix	225	3% Ca CL2

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production None	Producing method (flowing, pumping, gas lift, etc.)			
RATE OF PRODUCTION PER 24 HOURS	Oil bbls.	Gas MCF	Water bbls.	Gas-oil ratio CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval (s) None	

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator William E. Wise		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: Dry Hole
Well No. 1	Lease Name Pioneer	
S 17 T 11 R 31 ^W _W		


WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
See Attached Geologist's Report for sample descriptions			Stone Corral	2537
			Topeka	3786
			Heebner	4007
			Toronto	4038
			LKC	4054
DST No. 1 (LKC)	4250	4270	Base LKC	4336
Times: 15-30-45-60			Marmaton	4370
Pressures: At 4227'			Pawnee	4463
HP 2071 - 2071			Fort Scott	4532
IF 23 - 23			Cherokee Sh	4558
FF 26 - 26			Cherokee SS	4628
SIP 150 - 409			Mississippian	4650
Recovery: 10' drilling mud			Logs:	
Misrun - Anchor perforations plugged			Gamma-Guard	4695 to surface
			SNP	
			GR - Density	4695 to 3500
			Caliper	

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received		X
	Signature	
	Title	
	Date 7/1/81	