


API #15-063-20, 142

7-11-31W

640 Acres
N



Locate well correctly

Lease Name: Wieland "D" Well No. 1
Well Located: C SE SE
Gove SEC 7 TWP 11S RGE 31W
Operator: Pickrell Drilling Company
Address: 705 Fourth National Bank Bldg., Wichita, Kansas
Elevation: Ground 3019' D.F. 3021' K.B. 3024'
Type Well: (Oil, gas, dry hole) Dry Hole

Drilling Commenced: 10/21/ 19 72 Drilling Completed: 10/31/ 19 72
Well Completed: 19 Total Depth 4655'
Initial Production: _____

Casing Record

Size: 8-5/8" Set at 251' Size: _____ Set at _____
Size: _____ Set at _____ Size: _____ Set at _____

Liner Record

Size: _____ Set from _____ To _____

Cementing

Casing Size	Sacks	Type Cement and Additives
<u>8-5/8"</u>	<u>150</u>	<u>3/2</u>
_____	_____	_____
_____	_____	_____

Perforations

Formation	Perforated Interval and Number Shots
_____	_____
_____	_____
_____	_____

Electric Log Run (Show type log and depths covered)

No Electric Log Run

(Fill in formation and related information on reverse side)

7-11-31W

FORMATION, TESTING AND COMPLETION RECORD

Show Drill Stem Tests,
Well Stimulation and
Production Tests

Formation	Top	Bottom
Surface Soil	0	100
Sand	100	150
Shale	150	2543
Anhydrite	2543	2575
Shale	2575	2780
Shale - Lime	2780	3225
Lim & Shale	3225	3375
Lim	3375	3570
Lime & Shale	3570	3995
Lime	3995	4055
Shale & Lime	4055	4097
Lim & Shale	4097	4284
Lim	4284	4355
Lime & Shale	4355	4600
Lime, RTD	4600	4655

DST # 1 4250-4284: Open 40 minutes, weak blow 11 minutes. Rec. 10' mud, no show. IBHP 180#/30", FBHP 84#/45", IFP 11#, FFP 32#.

100	Surface Soil
150	Sand
2780	Shale
3225	Shale - Lime
3375	Lime & Shale
3570	Lime
3995	Lime & Shale
4055	Lime
4097	Shale & Lime
4284	Lime & Shale
4355	Lime
4600	Lime & Shale
4655	Lime, RTD

C.F.S.

3980
4055
4075
4097
4115
4143
4157
4175
4230
4260
4284
4310
4345
4390
4655

SMP TOPS

SC	2543
Top	3788
Heebner	4013
Tor	4042
Lansing	4058
KC	4214
Stark	4281
BKC	4343
Marm	4376
Pawn	4476
Ft Sc	4545
Cher	4575
RTD	4660

Slope Tests

2000
2500
3000
3500
4000
4500