


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- SKILES OIL CORP.
Farm- Sharp No. 1

SEC. 15 T. 11 R. 32W
SE SE SE

Total Depth. 4761
Comm. 11-18-51 Comp. 2-7-52
Shot or Treated.
Contractor.
Issued. 3-8-52

County Logan KANSAS



CASING:
10 3/4" 176' cem. w/200 sx
5 1/2" 4690' cem. w/125 sx

Elevation. 3017 K.B.
3045(m)

Production. Dry

Figures indicate Bottom of Formations.

surface sand	250
shale & shells	1670
shale & sand	2030
shale & lime	2665
shale, lime & salt	2945
shale & lime	3590
lime	3668
sand, shale & lime	3757
lime & shale	3829
lime & sand	3898
lime & shale	3963
lime	4268
lime & shale	4296
lime	4641
lime & sand	4668
lime	4761 RTD
Total Depth	

Tops:

Topeka Lime	3790
Heebner Shale	4042
Lansing-K.C. Lime	4064
Marmaton	4352
Patterson Sand	4629
Miss. Lime	4657

Perf. 4652-4658 24 shots
about 1/2 bbls. of oil per hr.
Plugged back to 4316'
Perf. 4290-4306'
Acidized with 1000 gals. wtr with
a show of oil