

KANSAS DRILLERS LOG


State Geological Survey
WICHITA, BRANCH

S. 18 T. 11 R. 32W E W

Loc. C SE

County Logan

640 Acres
N



Locate well correctly

Elev.: Gr. 3082

DF 3084 KB 3087

API No. 15 — 109 — 20065
County Number

Operator
Donald C. Slawson

Address
408 120 Bldg. Wichita, Ks. 67202

Well No. 1 Lease Name Lintel 'C'

Footage Location
feet from (N) (S) line feet from (E) (W) line

Principal Contractor Slawson Drlg. Co., Inc. Geologist George Mueller

Spud Date March 21, 1976 Total Depth 4643 P.B.T.D.

Date Completed March 30, 1976 Oil Purchaser N/A

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4	8 5/8"		263	60/40 Poz	200 sx	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
RATE OF PRODUCTION PER 24 HOURS	Oil bbls.	Gas MCF	Water bbls.	Gas-oil ratio	CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Donald C. Slawson		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. 1	Lease Name Lintel 'C'	Dry Hole
S 18 T 11 R 32W E W		


WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Surface Hole	0	270		
Shale & Shells	270	2502		
Shale & Lime	2502	2581		
Anhydrite	2581	2610		
Shale & Lime	2610	4085		
Lime	4085	4630		
RTD	4630			
<p>DST #1 4228-4260 (160' zn). 30-30-30-30, WB/died 15", Rec. 5' M, IFP 37-37#, ISIP 1258#, FFP 37-37#, FSIP 1202# Drlg @ 4303'</p> <p>Drlg @ 4571'</p> <p>DST #2 4558-4643 (JH ZN), 30-45-45-60, WB-GB, Rec. 1890' GIP, 155' VSOsptdM, 190' MSW, IFP 74-176#, ISIP 768#, FFP 176-213#, FSIP 556#</p>				
<p align="right">LOG TOPS ANH 2592 (+495) B/ANH 2619 (+468) HEEB 4018 (-931) TCRO 4049 (-962) LANS 4060 (-973) STK 4281 (-1194) B/KC 4337 (-1250) PAWN 4477 (-1390) U/CK 4533 (-1446) L/CK 4566 (-1479) JH ZN 4610 (-1523) LTD 4641 (-1554)</p>				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	<p align="center">  Rene M. Stucky Engineering Assistant Title April 14, 1976 Date </p>
---------------	--

810101

State Geological Survey
WICHITA, BRANCH WELL LOG

OPERATOR: Donald C. Slawson
408 120 Bldg.
Wichita, Ks. 67202

LEASE: #1 Lintel 'C'
C SE Sec. 18-11-32W
Logan Co., Ks.

CONTRACTOR: Slawson Drlg. Co., Inc.

COMMENCED: March 21, 1976

COMPLETED: March 30, 1976

CASING: Set 8 5/8" @ 263 w/200 sx

TOTAL DEPTH: 4643 feet

0 - 270	Surface Hole
270 - 2593	Shale & Shells
2593 - 2610	Anhydrite
2610 - 2621	Anhydrite
2621 - 3055	Shale & Shells
3055 - 4260	Shale & Lime
4260 - 4643	Lime
4643	RTD

STATE OF KANSAS)
) SS.
COUNTY OF SEDGWICK)

I, RENE M. STUCKY, of the Slawson Drilling Company, Inc. upon oath state that the above and foregoing is a true and correct copy of the log of the #1 Lintel 'C' well.