

State Geological Survey

WICHITA, BRANCH

KANSAS DRILLERS LOG

S. 22 T. 11 R. 33W ^E/_W

API No. 15 — Logan ¹⁰⁹ 20 062
County Number

Loc. C NE SE
 County Logan

Operator
Donald C. Slawson

Address
408 120 Bldg. Wichita, Ks. 67202


Well No. 1 Lease Name Scheetz 'A'

Footage Location
feet from (N) (S) line feet from (E) (W) line

Principal Contractor Slawson Drlg. Co., Inc. Geologist Ralph Ruwwe

Spud Date Feb. 19, 1976 Total Depth 4675 P.B.T.D.

Date Completed March 3, 1976 Oil Purchaser N/A



Elev.: Gr. 3138
 DF 3140 KB 3143

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"		258	60/40 Poz	200 sx	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	bbls.	MCF	bbls.	CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Donald C. Slawson		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. 1	Lease Name Scheetz 'A'	Dry Hole
S 22 T 11 R 33W ^E _W		

WELL LOG


Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Surface Hole	0	261	LOG TOPS	
Shale & Shells	261	2605	ANH 2632	(+511)
Shale	2605	2634	B/ANH 2659	(+484)
Anhydrite	2634	2658	WAB 3699	(-556)
Shale	2658	2700	HEEB 4051	(-908)
Lime	2700	4675	TORO 4076	(-933)
RTD	4675		LANS 4095	(-952)
			STK 4320	(-1177)
			B/KC 4384	(-1241)
			MARM 4415	(-1272)
			PAWN 4523	(-1380)
			U/Ck 4573	(-1430)
			L/CK 4607	(-1464)
			JH ZN 4652	(-1509)
			LTD 4676	(-1533)
<p>DST #1 4056-4088 (TORO), 30-45-45-60, W-GB, Rec. 170' VSOCMW (60% W, 35% M, 5% O), IFP 32-63#, ISIP 1226#, FFP 63-91#, FSIP 1207# Drlg @ 4118'</p> <p>DST #2 4222-64, (120&140' zn), 30-45-45-60, WBTO, Rec. 40' OCM (10% O) IFP 36-41#, ISIP 1189#, FFP 41-45#, FSIP 1189#,</p> <p>DST #3 4261-95 (160' zn), 30-30-30-30, VWB/30", Rec. 15' OCM (10% O), IFP 32-36#, ISIP 1108#, FFP 36-36#, FSIP 1017#</p> <p>DST #4 4287-4323 (180' zn) 45-60-60-75, FB inc SB, Rec. 450' TF, 140' OCMW (10% O, 70% W, 310' CW, IFP 36-145#, ISIP 1307#, FFP 154-227#, FSIP 1271#</p> <p>DST #5 4315-4350 (200' zn) 30-45-45-60, WBTO, Rec. 40' OCM (10% O), IFP 36-41#, ISIP 1362#, FFP 41-45#, FSIP 1353#</p>				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.




 Rene M. Stucky Signature
 Engineering Assistant
Title
 March 22, _____
Date

101364

22-11-33W
15-109-20,062

OPERATOR: Donald C. Slawson
408 120 Bldg.
Wichita, Kansas 67202

LEASE: #1 Scheetz 'A'
C NE SE Sec. 22-11-33W
Logan Co., Kansas

CONTRACTOR: Slawson Drilling Company, Inc.

COMMENCED: February 19, 1976

COMPLETED: March 3, 1976

CASING: Set 8 5/8" A 258 w/200 sx

TOTAL DEPTH: 4675 feet

0 - 261	Surface Hole
261 - 2605	Shale & Shells
2605 - 2634	Shale
2634 - 2658	Anhydrite
2658 - 2700	Shale
2700 - 4675	Lime
4675	RTD

STATE OF KANSAS)
) SS.
COUNTY OF SEDGWICK)



I, RENE M. STUCKY, of the Slawson Drilling Company, Inc. upon oath state that the above and foregoing is a true and correct copy of the log of the #1 Sheetz 'A' well.

Rene M. Stucky

RENE M. STUCKY

Subscribed and sworn to before me this 22nd day of March, 1976