

KANSAS DRILLERS LOG

API No. 15

County

Number

Operator

Donald C. Slawson

Address

200 Douglas Building, Wichita, Kansas 67202

Well No.

#1

Lease Name

James 'E'

Footage Location

2340'

feet from (N) (S) line

1010'

feet from (E) (W) line

Principal Contractor

Slawson Drilling Co., Inc.

Geologist

Ralph Ruwwe

Spud Date

2/18/78

Total Depth

4800'

P.B.T.D.

N/A

Date Completed

March 3, 1978


Oil Purchaser

N/A

S. 25 T. 11 R. 33W E

Loc. SE SW NW

County Logan

640 Acres
N

Locate well correctly

Elev.: Gr. 3106

DF 3108 KB 3111

CASING RECORD

Report of all strings set—surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 $\frac{1}{4}$ "	8 5/8"	28#	317'	60/40 poz	275	3% gel, 2% cc

LINER RECORD

Top, ft.	Bottom, ft.	Sacks cement

PERFORATION RECORD

Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production Producing method (flowing, pumping, gas lift, etc.)

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	bbls.	MCF	bbls.	CFPB

Disposition of gas (vented, used on lease or sold)

Producing interval (s)

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Donald C. Slawson		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: dry hole
Well No. #1	Lease Name James 'E'	
S 25 T 11 R 33W E W		


WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
0 - 322 Surface hole 322 - 730 Shale, sand and shells 730 - 1625 Shale and shells 1625 - 1675 Shale 1675 - 1823 Shale and shells 1823 - 2145 Shale and sand 2145 - 2504 Shale 2504 - 2615 Shale and shells 2615 - 2643 Anhydrite 2643 - 2677 Shale and shells 2677 - 4509 Lime and shale 4509 - 4800 Lime 4800 RTD			LOG TOPS ANH 2614 (+497) B/ANH 2641 (+470) WAB 3678 (-567) HEEB 4033 (-922) TORO 4054 (-943) LANS 4071 (-960) ST SH 4288 (-1177) B/KC 4348 (-1237) MARM 4385 (-1274) PAWN 4494 (-1383) L/CK 4579 (-1468) JH ZN 4622 (-1511) CG 4662 (-1551) MISS 4684 (-1573) LTD 4800	
DST #1 4136-4160 (70' zn), 30-45-45-60, WB, Rec. 30' CO 33°, 60' Tn SOCM (BGO 5% O, 80% M, 15% W), IFP 30-41#, ISIP 1245#, FFP 41-61#, FSIP 1205#				
DST #2 4259-4293 (180' zn), 30-45-30-45, VWB/40", Rec. 25' SOCM, IFP 31-31#, ISIP 796#, FFP 41-41#, FSIP 132#, 115°				
DST #3 4282-4325 (200' zn) 30-45-45-60, W-FB, Rec. 1' O 37°, 30' SOCM, 95' MW, IFP 41-61#, ISIP 1338#, FFP 61-92#, FSIP 1297#, 118°				
DST #4 4569-4645 (JH ZN), 30-45-30-30, VWB/32", Rec. 30' M, NS, IFP 61-61#, ISIP 1082#, FFP 61-61#, FSIP 755#, 122°				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	 Signature	
	R.J. Thatcher	
	Title	
	March 16, 1978 Date	

485201