

15-109-20108

KANSAS DRILLERS LOG

S. 26 T. 11 R. 33W ^E/_W
 Loc. SE NW NW
 County _____

API No. 15 _____
 County _____ Number _____

Operator
DONALD C. SLAWSON

Address
200 Douglas Building Wichita, Kansas 67202


Well No. 2 Lease Name
Bertrand 'G'

Footage Location
990' feet from (N) (S) line 1000' feet from (E) (W) line

Principal Contractor
Slawson Drilling Co. Inc. Geologist
George Mueller

Spud Date
July 26, 1978 Total Depth
4775' P.B.T.D. _____

Date Completed
August 5, 1978 Oil Purchaser
N/A



640 Acres
 N
 Locate well correctly
 Elev.: Gr. 3130
 DF 3133 KB 3135

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4	8 5/8"	28#	371'	60/40 poz	275	2% gel, 3% cc

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production _____		Producing method (flowing, pumping, gas lift, etc.) _____			
RATE OF PRODUCTION PER 24 HOURS	Oil _____ bbls.	Gas _____ MCF	Water _____ bbls.	Gas-oil ratio _____	CFPB _____
Disposition of gas (vented, used on lease or sold) _____			Producing interval (s) _____		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator DONALD C. SLAWSON		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. 2	Lease Name Bertrand 'G'	Dry Hole
S 26 T 11 R 33WE W		


WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
0 - 376 Surface			<u>LOG TOPS</u>	
376 - 1455 Shale and Shells			ANH 2628 (+507)	
1455 - 2093 Shale and Sand			B/ANH 2653 (+478)	
2093 - 2628 Shale and Shells			HEEB 4040 (-905)	
2628 - 2653 Anhydrite			TORO 4068 (-933)	
2653 - 2688 Shale and Shells			LANS 4078 (-943)	
2688 - 4145 Lime and Shale			STK SH 4302 (-1167)	
4145 - 4325 Lime			B/KC 4358 (-1223)	
4325 - 4470 Shale and Lime			MARM 4391 (-1256)	
4470 - 4554 Lime			PAW 4500 (-1365)	
4554 - 4650 Shale and Lime			L/CHER 4580 (-1445)	
4650 - 4670 Lime			solid MISS 4689 (-1554)	
4670 - 4775 Lime and Shale			LTD 4770 (-1635)	
4775 RTD				
<p>DST #1 4247-4280 (160 Zn) WkB/12", 30-30-30-30, Rec. 10' M, IFP 36-36#, ISIP 36#, FFP 36-36#, FSIP 36#, DST #2 4273-4305 (180 Zn) Pkr failed. DST #3 4247-4305 (180 Zn) Incr Blow, 30-60-45-75, Rec 1 pt O, 250' SW, 85' MSW, 335' total. IFP 52-96#, ISIP 1157#, FFP 104-157#, FSIP 1139#. DST #4 4296-4325 (200 Zn) 30-30-30-30, Wk/30", Rec. 2' O, 18' M, IFP 27-36#, ISIP 126#, FFP 36-36#, FSIP 54#. Drlg @ 4554' DST #5 4572-4650 (JH ZN) WkB/55" Rec. 60' SOCM, IFP 52-70#, ISIP 1113#, FFP 70-78#, FSIP 470#. Drlg @ 4704'</p>				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	 Signature R. J. THATCHER - Engineer Title September 28, 1978 Date
---------------	---

