


**KANSAS DRILLERS LOG**

S. 32 T. 11 R. 33W<sup>E</sup><sub>W</sub>

Loc. S/2 SE NW

County Logan

640 Acres  
N



Locate well correctly  
3127

Elev.: Gr. \_\_\_\_\_

DF 3129 KB 3132

API No. 15 — \_\_\_\_\_ County \_\_\_\_\_ Number \_\_\_\_\_

Operator  
Donald C. Slawson

Address  
408 One Twenty Building

Well No. 1 Lease Name Bertrand 'J'

Footage Location  
2360 feet from (N) (S) line 1980 feet from (E) (W) line

Principal Contractor Slawson Drilling Co., Inc. Geologist George Mueller

Spud Date May 16, 1977 Total Depth 4800' P.B.T.D. N/A

Date Completed May 26, 1977 Oil Purchaser N/A

**CASING RECORD**

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"	28#	266'	60/40 poz	175	2% gel, 3% cc

**LINER RECORD**

**PERFORATION RECORD**

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

**TUBING RECORD**

Size	Setting depth	Packer set at

**ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD**

Amount and kind of material used	Depth interval treated

**INITIAL PRODUCTION**

Date of first production _____		Producing method (flowing, pumping, gas lift, etc.) _____			
RATE OF PRODUCTION PER 24 HOURS	Oil _____ bbls.	Gas _____ MCF	Water _____ bbls.	Gas-oil ratio _____	CFPB _____
Disposition of gas (vented, used on lease or sold) _____			Producing interval (s) _____		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Donald C. Slawson DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: dry hole

Well No. 1 Lease Name Bertrand 'J'

S 32 T 11 R 33W<sup>E</sup><sub>W</sub>


**WELL LOG**

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
0 - 270 Surface hole			<u>LOG TOPS</u>	
270 - 1805 Shale and shells				
1805 - 3467 Shale				
3467 - 4065 Shale and Lime			ANH 2608 (+524)	
4065 - 4395 Lime			B/ANH 2635 (+497)	
4395 - 4510 Lime and shale			HEER 4028 (-896)	
4510 - 4800 Lime			TORO 4052 (-920)	
4800 RTD			LANS 4065 (-933)	
			STK 4297 (-1155)	
			B/KC 4358 (-1226)	
			PAWN 4493 (-1359)	
			L/CK 4580 (-1448)	
			JH ZN 4624 (-1492)	
			SD 4680 (-1548)	
			MISS 4698 (-1566)	
			LTD 4800	
DST #1 4036-4065 (TORO), 30-30-30-30, VWB 15"/died, Rec. 5' O, 40' MSW, IFP 37-56#, ISIP 1156#, FFP 56-56#, FSIP 1063#				
DST #2 4063-4085 (TOP zn), GBTO, 30-45-45-60, Rec. 650' MSW, IFP 37-187#, ISIP 1287#, FFP 187-317#, FSIP 1250#				
DST #3 4142-4173 (70-90' zn), 30-45-45-60, FB, Rec. 30' O, 90' MSW, IFP 37-56#, ISIP 1306#, FFP 56-93#, FSIP 1287#				
DST #4 4200-4245 (140' zn), 30-30-30-30, VB/15"/died, Rec. 30' M, NS, IFP 37-37#, ISIP 1283#, FFP 37-37#, FSIP 1249#				
DST #5 4244-4297 (160-180' zn) 30-45-45-60, SBTO, Rec. 630' MSW, IFP 37-187#, ISIP 1362#, FFP 187-317#, FSIP 1343#				
DST #6 4290-4113 (200' zn), 30-45-45-60, GBTO, Rec. 430' MSW, IFP 37-103#, ISIP 1399#, FFP 112-196#, FSIP 1306#				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	
	R.J. Thatcher
	Title
	June 3, 1977
	Date

117201