

**KANSAS DRILLERS LOG**

API No. 15 — 109 — 20051  
 County Number

S. 14 T. 11 R. 33W <sup>E</sup>/<sub>W</sub>

Loc. SW NW SE

County Logan

Operator

Donald C. Slawson

*State Geological Survey*  
**WICHITA BRANCH**

Address

408 120 Bldg. Wichita, Ks. 67202

Well No.

1

Lease Name

Ahrens 'A'

Footage Location

feet from (N) (S) line

feet from (E) (W) line

Principal Contractor

Slawson Dlr. Co., Inc.

Geologist

Ralph Ruwwe

Spud Date

Nov. 8, 1975

Total Depth

4649'


P.B.T.D.

Date Completed

Nov. 22, 1975

Oil Purchaser

N/A



Locate well correctly

Elev.: Gr. 3117

DF 3120 KB 3122

**CASING RECORD**

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"		256'	60/40 Poz	225 sx	

**LINER RECORD**

**PERFORATION RECORD**

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

Size	Setting depth	Packer set at

**ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD**

Amount and kind of material used	Depth interval treated

**INITIAL PRODUCTION**

Date of first production	Producing method (flowing, pumping, gas lift, etc.)
<b>RATE OF PRODUCTION PER 24 HOURS</b>	Oil Gas Water Gas-oil ratio
	bbls. MCF bbls. CFPB
Disposition of gas (vented, used on lease or sold)	Producing interval(s)

**INSTRUCTIONS:** As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

90738

Operator Donald C. Slawson		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: Dry Hole
Well No. 1	Lease Name Ahrens 'A'	
S 14 T 11 R 33W E W		

**WELL LOG**

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
			EL Tops	
Surface Hole	0	260	Anh	2611 (+511)
Shale & Shells	260	3139	B/ Anh	2638 (+484)
Shale	3139	3390	Wab	3677 (-555)
Shale & Lime	3390	4144	Heeb	4033 (-911)
Lime	4144	4649	Toro	4061 (-939)
RTD	4649		Lans	4074 (-952)
			Stk	4296 (-1174)
			B/KC	4356 (-1234)
			Marm	4387 (-1265)
			Alta	4449 (-1327)
			Paw	4498 (-1376)
			Chk	4580 (-1458)
			Jh Zn	4625 (-1503)
			Ltd	4651 (-1529)
DST #1 4205-4275 (120-140-160 zns), 30-45-45-60, Rec. 120' GIP, 170' WM, 125' W, IFP 71-125#, IBHP 627#, FFP 134-179#, FBHP 600#.				
DST #2, #3, #4, 4266-90 (couldn't get to bottom)				
DST #5 4266-90, (180' zn), 30-60-45-60, Rec. 90' 0 sptd M w/scum 0 on top, IFP 36-45#, IBHP 977#, FFP 45-72#, FBHP 923#.				
DST #6 4292-4330, (200' zn), 30-45-45-60, Rec. 130' GIP, 155' VHOCM, IFP 27-63#, IBHP 780#, FFP 63-97#, FBHP 762#.				
DST #7 4574-4649, Tool opened w/VWB, 30-50-30-60, Rec. 30' Mud w/spts of 0, IBHP 104#, IFP 17-26#, FBHP 69#, FFP 26-26#.				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	<p><i>James C. Remsburg</i></p> <p>James C. Remsburg Petroleum Engineer Title</p> <p>December 2, 1975 Date</p>
---------------	--