

**WELL COMPLETION REPORT AND
DRILLER'S LOG**

API No. 15 — 109 — 20,151
County Number

Operator
DONALD C. SLAWSON

Address
200 Douglas Building Wichita, Kansas 67202

Well No. 1 Lease Name Schertz 'B'

Footage Location
2290 feet from (N) (S) line 320 feet from (E) (W) line

Principal Contractor SLAWSON DRILLING CO., INC. Geologist Jeff Stewart

Spud Date 9/2/80 Date Completed 9/13/80 Total Depth 4780' P.B.T.D. N/A


Directional Deviation _____ Oil and/or Gas Purchaser N/A

State Geological Survey
S. 25 T. 11 R. 34 E

Loc. SE SE NE

County Logan

640 Acres
N



Locate well correctly

Elev.: Gr. 3123

DF 3126 KB 3129

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Socks	Type and percent additives
SURFACE	12 1/4"	8 5/8"		328'	60/40 poz	225 sx	2% gel, 3% cc

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

Size	Setting depth	Pecker set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production _____	Producing method (flowing, pumping, gas lift, etc.) _____
RATE OF PRODUCTION PER 24 HOURS _____	Oil _____ bbls. Gas _____ MCF Water _____ bbls. Gas-oil ratio _____ CFPB
Disposition of gas (vented, used on lease or sold) _____	Producing interval (s) _____

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

90218

Operator DONALD C. SLAWSON		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. 1	Lease Name Schertz 'B'	Dry Hole
S 25 T 11 R 34W E W		

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
0 - 331 Surface				
331 - 2595 Shale			<u>LOG TOPS</u>	
2595 - 2781 Anhydrite			ANHY 2597 (+532)	
2781 - 3178 Shale			B/ANHY 2625 (+504)	
3178 - 4105 Shale and lime			WAB 3656 (-527)	
4105 - 4145 Lime			HEEB 4018 (-839)	
4145 - 4158 Lime and shale			TORO 4046 (-917)	
4158 - 4262 Lime			LANS 4059 (-930)	
4262 - 4296 Lime and shale			MUN CRK 4209 (-1080)	
4296 - 4312 Lime			STK SH 4296 (-1167)	
4312 - 4635 Lime and shale			B/KC 4356 (-1227)	
4635 - 4703 Lime			MARM 4393 (-1264)	
4703 - 4747 Lime and shale			PAW 4482 (-1353)	
4747 - 4780 Lime			FT SC 4546 (-1417)	
4780 RTD			L/CHER 4576 (-1447)	
DST #1 4046-4105 (Top Zn & 35' Zn)			JH ZN 4621 (-1492)	
30-30-30-30, VWkB?? Partial packer failure on initial flow, then held, blow very weak. Rec. 50' SW, 1170' WM, IFP 93-444#, ISIP 1241#, FFP 454-558#, FSIP 1220#, HP 1939-1929#.			ALTA 4646 (-1517)	
DST #2 4134-4145 (70' Zn)			MOR 4666 (-1537)	
30-30-30-30, Strong blow on initial flow due to packer trying to fail, then became very weak blow. Rec. 365' Mud, IFP 52-186#, ISIP 1116#, FFP 186-186#, FSIP 1033#, HP 1908-1929#.			MISS 4704 (-1575)	
DST #3 4235-4262 (140' Zn)			LTD 4784 (-1655)	
45-30-40-30, WkB, Rec. 60' OCM-10% Oil, 60' SOCM, 60' WM, the tool would not rotate and close.				
DST #4 4234-4312 (160' 180' & 200' Zn)				
30-45-45-60, Strg B, Rec. 115' Mud w/a trace of oil, 185' MSW, 620' SW, IFP 41-238#, ISIP 1314#, FFP 248-455#, FSIP 1262#, HP 2065-2044#.				
			DST #5 4561-4635 (JH ZN) 30-30-30-30, VWkB/died, Rec. 30' Mud, IFP 41-41#, ISIP 1033#, FFP 52-52#, FSIP 971#, HP 2285-2264#.	

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	<p align="center"><i>James C. Remsberg</i> JAMES C. REMSBERG, Oper. Mgr.</p>
	<p align="center">October 21, 1980</p>
	<p align="center">Title</p>
	<p align="center">Date</p>