

State Geological Survey

KANSAS DRILLERS LOG WICHITA, BRANCH


S. 36 T. 11 R. 34 E
W

Loc. C SE NW

PI No. 15 — 109 — 20,034
County Number

County Logan

640 Acres
N



Locate well correctly

Elev.: Gr. 3179'

DF 3182' KB 3184'

Operator
Abercrombie Drilling, Inc.

Address
801 Union Center Building Wichita, Kansas 67202

Well No. #1 Lease Name Colglazier

Footage Location
1980 feet from (N) line 1980 feet from (W) line

Principal Contractor Abercrombie Drilling, Inc. Geologist George Dent

Spud Date March 29, 1975 Total Depth 4790' P.B.T.D.

Date Completed April 7, 1975 Oil Purchaser None

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/2"	8-5/8"		270.65'	Sunset	175	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production Producing method (flowing, pumping, gas lift, etc.)

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	bbls.	MCF	bbls.	CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval(s)	

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3930 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2205. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on an open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator
Abercrombie Drilling, Inc.

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:

Well No. 1 Lease Name COLGLAZIER

DRY HOLE

S 36 T 11S R 34 K
W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Surface Dirt & Sand	0	240	ELECTRIC LOG TOPS:	
Shale	240	2653		
Anhydrite	2653	2685	Anhydrite	2654
Shale	2685	3305	B/Anhydrite	2678
Shale & Lime	3305	3515	Heebner	4069
Lime	3515	3560	Lansing	4110
Shale & Lime	3560	3680	B/Kansas City	4405
Lime & Shale	3680	3910	Marmaton	4444
Lime	3910	4790	Mississippi	4750
Rotary Total Depth		4790	ELTD	4790
No Drill Stem Tests Taken.				
Plugged & Abandoned:				
1st Plug Set @1500' w/70 sx. 50/50 Posmix, 6% gel				
2nd Plug Set @ 270' w/20 sx.				
3rd Plug Set @ 40' w/10 sx.				
Plug down @ 6:00 p.m., 4-7-75, State Plugger:				
Gilbert Balthazor				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received
JUL 1975

RECEIVED
STATE GEOLOGICAL
SURVEY OF
KANSAS

Signature
Executive Vice President

Date
April 16, 1975

Title

Date