

DX 78-1

Trego

KANSAS

Section 4 Township 11 Range 23 W

Well No. # 4 Osborn

Company Imperial Drlg. Co.

NORTH

	0						

WEST

EAST

SOUTH

5

County **Trego** State **Kansas**
 Sec. **4** (Blk. **11**) (Sur. Rge.) **23W** Map No.
 Operator **Imperial Drlg.**
 Well No. **4** Farm **Osborn**
 Elev. **2317** Location **NE SW NW**

990 Ft. From **S** Line **NW**
 990 Ft. From **W** Line **Quarter**
 Ist. Report
 Completion **NOV 23 1954**
 Remarks **Wakeeney Pool**
Co. tools
 Spudding Date **9-28-54**

Drlg. Data **Oil well TD 3790**
8" @ 214 Anhy 1790 Heeb. 3511
Lans. 3547 DST 3574-92 open 1 hr.
Rec. 25' muddy wtr. 185' clean oil
185' sw 680# DST 3596-3605 open 1 hr.
Rec. 2730' gas 300' oil 75' hocom
124' sw 700# DST 3630-48 open 1 hr.
Rec. 62' mud 1190# DST 3652-60 open
1 hr. Rec. 1050' sw 1120# TD 3790
5" @ 3790 CO to 3790 - 30/-3766-70
500 A S/ 10 3/4 bo. 1 hr. - FU 1100' oil
S/ 3 3/4 boph - 2 hr. A-frac S/ 17 1/2 bo.
SP 3760 18/ 3750-53 500 A FU 800' oil
CO 3790 S/ 21 boph SP 3724 24/ 3710-14
2 goph 500 A FU 1900' oil S/ 19 boph
Comp. 265 bopd 17% wtr.

FABEN GU STDAD