

JOHN O. FARMER, INC.

P.O. Box 352

Russell, KS 67665

(785) 483-3144

Distribution:

W.C. Talbott
Pinnacle Resources
Aven Weaverling
Andrea Krauss
Murfin Drilling Co.
Nancy Talbott

Trapp B #2

1,850' FNL & 1,460' FWL

Sec. 8-12S-13W

Russell County, Kansas

1,628 'G.L.

1,636 'K.B.

(Splawn 2 3-D)

Drilling Contractor:**Discovery Drilling - Rig #2**

Cell. 785-635-1412

Toolpusher - Dave Dreiling

Geologist - Brad Hutchison

Cell 785-483-0492

Office 785-483-5783

API #15-167-23,408-0000

TIGHT HOLE - DO NOT RELEASE INFORMATION**1/24/2007**

MIRU, Spud 12 1/4" @ 7 PM; drill 413', ran 10 jts new 8 5/8" (403') set @ 413', cemented by Quality w/ 210 sx common 2% gel 3% CC, cement did circulate.

1/25/2007

413', running 8 5/8" casing

1/26/2007

1,620', drilling

1/27/2007

2,346', drilling

1/28/2007

2,900', running DST #1

DST #1- 2,850'-2,900 (Lansing B & C zones)

30" - 30" - 30" - 30"

IF- Weak Surface blow built to 1.5", no blow back

FF- Weak surface blow, died in 5", no blow back

Rec: 6" Oil Cut Mud (20% Oil, 80% Mud)

FP: 12-15#, 20-25#

SIP: 33-137#

HP: 1,387-1,351#

BHT: 88° F

DST #2- 2,852'-2,954 (Lansing B, C & G zones)

30" - 30" - 60" - 60"

IF- Bottom of bucket in 4", slight blow back

FF- Bottom of bucket in 3", slight blow back

Rec: 1,230' slightly muddy gassy saltwater

FP: 35-333#, 335-650#

SIP: 816-818#

HP: 1,387-1,357#

BHT: 95° F

1/29/2007

3,139' drilling

1/30/2007

3,450', laying down drill pipe

1/31/2007

3,450', job complete, casing run in well

Ran 81 Joints of new 14#- 5 1/2" Casing, set at 3,443' KB. Cemented by Allied with 200 sx Common, 10% Salt. Completed at 1:30 pm on 1/30/2007. Released rig at 2:00 pm.

John O. Farmer, Inc.			Estim.		JOHN O. FARMER, INC.			
Trapp B #1			from		Trapp B #2			
SE SW NW			3D		1636			
1657 KB			Seismic		Sample		E-Log	
Anhydrite	709	948			697	939	696	940
Topeka	2574	-917			2560	-924	2563	-927
Heebner	2802	-1145	-1145		2789	-1153	2792	-1156
Toronto	2821	-1164			2805	-1169	2811	-1175
Lansing	2856	-1199	-1199		2842	-1206	2847	-1211
B/KC	3134	-1477			3120	-1484	3123	-1487
Arbuckle	3380	-1723			3376	-1740	3380	-1744
RTD					3450	-1814		
LTD	3440	-1783					3452	-1816

OG-TECH**Dual Compensated
Porosity Log**



TAL LOG


Ph. (785) 625-3858

Wulf Co.

Company		John O. Farmer, Inc.	
Well		Trapp "B" #2	
Field		Wildcat	
County		Russell	State Kansas
Location		1850' FNL & 1460' FWL	
Sec: 8		Twp: 12S	Rge: 13W
ent Datum		Ground Level	Elevation 1628
asured From		Kelly Bushing	8 Ft. Above Perm. Datum
Measured From		Kelly Bushing	
			K.B. 1636 D.F. 1628 G.L. 1628
		1 / 29 / 2007	
mber		Two	
og		CNL / CDL	
Driller		3450	
ogger		3452	
Logged Interval		3432	
ged Interval		2350	
uid In Hole		Chemical	
ity, PPM CL		6,000	
sity		9.3	
l		Full	
ec. Temp. F		107	
ng Rig Time		4 Hours	
ent -- Location		4 Hays	
ed By		J. Loffredi	
ed By		Brad Hutchison	
Borehole Record			
Bit	From	To	Size Wgt.
12.25	00	413	8.625 24#
7.875	413	TD	
Casing Record			
	From	To	
	00	413	

<< Fold Here >>






3250

3300

3350

3400




26

27

27

24




3250

3300

3350

3400

3450



52

52

52

52

35